

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐
(highlight changes)

APPLICATION FOR PERMIT TO DRILL				5. MINERAL LEASE NO: ML-3282-A	6. SURFACE: Indian
1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>				7. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE TRIBE	
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input checked="" type="checkbox"/>				8. UNIT or CA AGREEMENT NAME: UNIT #891008900A	
2. NAME OF OPERATOR: KERR MCGEE OIL & GAS ONSHORE L.P.				9. WELL NAME and NUMBER: NBU 921-16P	
3. ADDRESS OF OPERATOR: 1368 S 1200 E CITY VERNAL STATE UT ZIP 84078				PHONE NUMBER: (435) 781-7024	10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 537' FSL, 610' FEL AT PROPOSED PRODUCING ZONE:				11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SESE 16 9S 21E	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 11.55 +/- MILES FROM OURAY, UTAH				12. COUNTY: UINTAH	13. STATE: UTAH
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 537'		16. NUMBER OF ACRES IN LEASE: 40.00		17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 40.00	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) REFER TO TOPO C		19. PROPOSED DEPTH: 10,130		20. BOND DESCRIPTION: RLB0005239	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 4817' GL		22. APPROXIMATE DATE WORK WILL START:		23. ESTIMATED DURATION:	

24. PROPOSED CASING AND CEMENTING PROGRAM							
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT			SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT		
12 1/4"	9 5/8	32.3#	H-40	2,500	315 SX CLASS G	1.18 YIELD	15.6 PPG
7 7/8"	4 1/2	11.6#	H-80	10,130	2060 SX 50/50 POZ	1.31 YIELD	14.3 PPG

25. ATTACHMENTS	
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:	
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER	<input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

NAME (PLEASE PRINT) SHEILA UPCHEGO TITLE SENIOR LAND ADMIN SPECIALIST
SIGNATURE [Signature] DATE 4/18/2007

(This space for State use only)


API NUMBER ASSIGNED: 43-047-39254

APPROVAL:

RECEIVED
APR 23 2007

T9S, R21E, S.L.B.&M.

2006 Alum.
Cap, 0.4'
High, Pile of
Stones



LEGEND:

- └─ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

(NAD 83)
LATITUDE = 40°01'49.17" (40.030325)
LONGITUDE = 109°32'58.18" (109.549494)
(NAD 27)
LATITUDE = 40°01'49.30" (40.030361)
LONGITUDE = 109°32'55.70" (109.548806)

Kerr-McGee Oil & Gas Onshore LP


Well location, NBU #921-16P, located as shown in the SE 1/4 SE 1/4 of Section 16, T9S, R21E, S.L.B.&M., Uintah County, Utah.

BASIS OF ELEVATION

TWO WATER TRIANGULATION STATION LOCATED IN THE NW 1/4 OF SECTION 1, T10S, R21E, S.L.B.&M. TAKEN FROM THE BIG PACK MTN NE, QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5238 FEET.


BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEY MADE BY ME UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



UINTAH ENGINEERING & SURVEYING
85 SOUTH 200 EAST - VERNAL, UTAH 84078
(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 01-24-07	DATE DRAWN: 01-31-07
PARTY L.K. J.M. S.L.	REFERENCES G.L.O. PLAT	
WEATHER WARM	FILE Kerr-McGee Oil & Gas Onshore LP	

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER



FORM APPROVED
OMB No. 1004-0136
Expires November 30, 2000

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. ML-3282-A
b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input checked="" type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name TRIBAL SURFACE
2. Name of Operator KERR MCGEE OIL AND GAS ONSHORE LP		7. If Unit or CA Agreement, Name and No. UNIT #891008900A
3A. Address 1368 SOUTH 1200 EAST VERNAL, UT 84078	3b. Phone No. (include area code) (435) 781-7024	8. Lease Name and Well No. NBU 921-16P
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface SE/SE 962'FSL, 491'FEL 623861X 40.031457 At proposed prod. Zone 4432 0484 -109.548352		9. API Well No. 43047-39254
10. Field and Pool, or Exploratory NATURAL BUTTES		11. Sec., T., R., M., or Blk. and Survey or Area SEC. 16, T9S, R21E
14. Distance in miles and direction from nearest town or post office* 11.55 +/- MILES FROM OURAY, UTAH		12. County or Parish UINTAH
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 537'		13. State UTAH
16. No. of Acres in lease 40.00	17. Spacing Unit dedicated to this well 40.00	
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. REFER TO TOPO C	19. Proposed Depth 10,130'	20. BLM/BIA Bond No. on file RLB0005239
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 4877'GL	22. Approximate date work will start* UPON APPROVAL	23. Estimated duration TO BE DETERMINED

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- | | |
|--|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification. |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office. | 6. Such other site specific information and/or plans as may be required by the authorized office. |

25. Signature 	Name (Printed/Typed) SHEILA UPCHEGO	Date 6/21/2007
Title SENIOR LAND ADMIN SPECIALIST		
Approved by (Signature) 	Name (Printed/Typed) BRADLEY G. HILL	Date 07-07-08
Title ENVIRONMENTAL MANAGER		


Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on reverse)

Federal Approval of this
Action is Necessary



T9S, R21E, S.L.B.&M.

2006 Alum.
Cap, 0.4'
High, Pile of
Stones

S89°58'20"E - 2638.41' (Meas.)

S89°58'47"E - 2638.37' (Meas.)

2006 Alum.
Cap, 3.0'
High, Pile of
Stones

2006 Alum.
Cap, 2.0'
High, Pile of
Stones

N00°08'41"E - 2649.54' (Meas.)

S00°13'14"W - 2658.16' (Meas.)

2006 Alum.
Cap, 1.0' High,
Pile of Stones

Set Marked
Stone

16

N00°02'14"W - 2647.34' (Meas.)

N00°17'27"W - 2632.19' (Meas.)

2006 Alum.
Cap, Pile of
Stones

2006 Alum.
Cap, 1.0' High,
Pile of Stones

2006 Alum.
Cap, 0.6'
High, Steel
Post

S89°59'13"E - 2644.46' (Meas.)

N89°53'15"E - 2640.94' (Meas.)

NBU #921-16P
Elev. Ungraded Ground = 4812'

491'
962'

LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

(NAD 83)
LATITUDE = 40°01'53.38" (40.031494)
LONGITUDE = 109°32'56.67" (109.549075)
(NAD 27)
LATITUDE = 40°01'53.51" (40.031531)
LONGITUDE = 109°32'54.19" (109.548386)

Kerr-McGee Oil & Gas Onshore LP


Well location, NBU #921-16P, located as shown in the SE 1/4 SE 1/4 of Section 16, T9S, R21E, S.L.B.&M. Uintah County, Utah.

BASIS OF ELEVATION


TWO WATER TRIANGULATION STATION LOCATED IN THE NW 1/4 OF SECTION 1, T10S, R21E, S.L.B.&M. TAKEN FROM THE BIG PACK MTN NE, QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5238 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



REVISED: 04-30-07 C.H.

UINTAH ENGINEERING & LAND SURVEYING
85 SOUTH 200 EAST - VERNAL, UTAH 84078
(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 01-24-07	DATE DRAWN: 01-31-07
PARTY L.K. J.M. S.L.	REFERENCES G.L.O. PLAT	
WEATHER WARM	FILE Kerr-McGee Oil & Gas Onshore LP	

**NBU 921-16P
SE/SE Sec. 16, T9S, R21E
UINTAH COUNTY, UTAH
ML-3282-A**

ONSHORE ORDER NO. 1

DRILLING PROGRAM

1. Estimated Tops of Important Geologic Markers:

<u>Formation</u>	<u>Depth</u>
Uinta	0- Surface
Green River	1633'
Top of Birds Nest Water	1959'
Mahogany	2321'
Wasatch	5008'
Mesaverde	7990'
MVU2	8917'
MVL1	9502'
TD	10,130'

2. Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>
	Green River	1663'
	Top of Birds Nest Water	1959'
	Mahogany	2321'
Gas	Wasatch	5008'
Gas	Mesaverde	7990'
Gas	MVU2	8917'
Gas	MVL1	9502'
Water	N/A	
Other Minerals	N/A	

3. Pressure Control Equipment (Schematic Attached)

Please see the Natural Buttes Unit Standard Operating Procedure (SOP).

4. Proposed Casing & Cementing Program:

Please see the Natural Buttes Unit SOP.

5. Drilling Fluids Program:

Please see the Natural Buttes Unit SOP.

6. Evaluation Program:

Please see the Natural Buttes Unit SOP.

7. **Abnormal Conditions:**

Maximum anticipated bottomhole pressure calculated at 10,130' TD, approximately equals 6281 psi (calculated at 0.62 psi/foot).

Maximum anticipated surface pressure equals approximately 4052 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

8. **Anticipated Starting Dates:**

Drilling is planned to commence immediately upon approval of this application.

9. **Variances:**

Please see Natural Buttes Unit SOP.

10. **Other Information:**

Please see Natural Buttes Unit SOP.



KERR-McGEE OIL & GAS ONSHORE LP **DRILLING PROGRAM**

COMPANY NAME KERR-McGEE OIL & GAS ONSHORE LP DATE April 18, 2007
WELL NAME NBU 921-16P TD 10,130' MD/TVD
FIELD Natural Buttes COUNTY Uintah STATE Utah ELEVATION 4,814' GL KB 4,829'
SURFACE LOCATION SE/SE SEC. 16, T9S, R21E 537'FSL, 610'FEL BHL Straight Hole
Latitude: 40.030325 Longitude: 109.549494
OBJECTIVE ZONE(S) Wasatch/Mesaverde
ADDITIONAL INFO Regulatory Agencies: TRIBAL (SURF & MINERALS), BLM, UDOGM, Tri-County Health Dept.

GEOLOGICAL			MECHANICAL		
LOGS	FORMATION	DEPTH	HOLE SIZE	CASING SIZE	MUD WEIGHT
		40'		14"	
			12-1/4"	9-5/8", 32.3#, H-40, STC	Air mist
			**For wells w/ surf csg set below 2200' app 10 js of 36# J55 will be run on bottom		
Catch water sample, if possible, from 0 to 5,008'					
	Green River @	1,633'			
	Top of Birds Nest Water @	1,959'			
	Mahogany @	2,321'			
	Preset f/ GL @				
	2,500' MD				
Note: 12.25" surface hole will usually be drilled ±400' below the bottom of lost circulation zone. Drilled depth may be ±200' of the estimated set depth depending on the acutal depth of the loss zone.					
Mud logging program TBD					
Open hole logging program f/ TD - surf csg					
	Wasatch @	5,008'			
	Mverde @	7,990'			
	MVU2 @	8,917'			
	MVL1 @	9,502'			
			7-7/8"	4-1/2", 11.6#, I-80 or equivalent LTC casing	Water/Fresh Water Mud 8.3-11.8 ppg
					Max anticipated Mud required 11.8 ppg
		TD @ 10,130'			



KERR-McGEE OIL & GAS ONSHORE LP **DRILLING PROGRAM**

CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'						
SURFACE	9-5/8"	0 to 2100	32.30	H-40	STC	2270 0.57*****	1370 1.39	254000 3.59
	9-5/8"	2100 to 2500	36.00	J-55	STC	3520 1.11*****	2020 1.73	564000 7.98
PRODUCTION	4-1/2"	0 to 10130	11.60	I-80	LTC	7780 1.95	6350 1.02	201000 1.96

- 1) Max Anticipated Surf. Press. (MASP) (Surface Casing) = (Pore Pressure at next csg point - (0.22 psi/ft-partial evac gradient x TVD of next csg point))
- 2) MASP (Prod Casing) = Pore Pressure at TD - (.22 psi/ft-partial evac gradient x TD)
- (Burst Assumptions: TD = 11.8 ppg) .22 psi/ft = gradient for partially evac wellbore
- (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing * Buoy. Fact. of water)
- MASP 3987 psi
- ***** Burst SF is low but csg is stronger than formation at 2500 feet
- ***** EMW @ 2500 for 2270# is 17.5 ppg or 0.9 psi/ft

CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE Option 1	LEAD	500	Premium cmt + 2% CaCl + .25 pps flocele	215	60%	15.60	1.18
	TOP OUT CMT (1)	250	20 gals sodium silicate + Premium cmt + 2% CaCl + .25 pps flocele	100		15.60	1.18
	TOP OUT CMT (2)	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
SURFACE Option 2	LEAD	2000	NOTE: If well will circulate water to surface, option 2 will be utilized Prem cmt + 16% Gel + 10 pps gilsonite + .25 pps Flocele + 3% salt BWOC	230	35%	11.00	3.82
	TAIL	500	Premium cmt + 2% CaCl + .25 pps flocele	180	35%	15.60	1.18
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
PRODUCTION	LEAD	4,500'	Premium Lite II + 3% KCl + 0.25 pps celloflake + 5 pps gilsonite + 10% gel + 0.5% extender	490	60%	11.00	3.38
	TAIL	5,630'	50/50 Poz/G + 10% salt + 2% gel +.1% R-3	1570	60%	14.30	1.31

*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe.
PRODUCTION	Float shoe, 1 jt, float collar. Centralize first 3 joints & every third joint to top of tail cement with bow spring centralizers.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. Test to 5,000 psi (annular to 2,500 psi) prior to drilling out. Record on chart recorder & tour sheet. Function test rams on each trip. Maintain safety valve & inside BOP on rig floor at all times. Kelly to be equipped with upper & lower kelly valves.

Drop Totco surveys every 2000'. Maximum allowable hole angle is 5 degrees.

Most rigs have PVT Systems for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER:

Brad Laney



DATE:

DRILLING SUPERINTENDENT:

Randy Bayne

DATE:

5M BOP STACK and CHOKE MANIFOLD SYSTEM



**NBU 921-16P
SE/SE SEC. 16, T9S, R21E
UINTAH COUNTY, UTAH
ML-3282-A**

ONSHORE ORDER NO. 1

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. Existing Roads:

Refer to the attached location directions.

Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

2. Planned Access Roads:

Please see the Natural Buttes Unit Standard Operating Procedure (SOP).

Approximately 0.15 +/- miles of new access road. Please refer to the attached Topo Map B.

3. Location of Existing Wells Within a 1-Mile Radius:

Please refer to Topo Map C.

4. Location of Existing & Proposed Facilities:

Please see the Natural Buttes Unit SOP.

Approximately 2739' +/- of 4" pipeline is proposed from the location to an existing pipeline.

All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded. The requested color is Carlsbad Canyon Brown (2.5Y 6/2), a non-reflective earthtone.

5. Location and Type of Water Supply:

Please see the Natural Buttes SOP.

6. Source of Construction Materials:

Please see the Natural Buttes SOP.

7. Methods of Handling Waste Materials:

Please see the Natural Buttes SOP.

Any produced water from the proposed well will be contained in a water tank and will then be hauled by truck to one of the pre-approved disposal sites: RNI, Sec. 5, T9S, R22E, NBU #159, Sec. 35, T9S R21E, Ace Oilfield, Sec. 2, T6S, R20E, MC&MC, Sec. 12, T6S, R19E (*Request is in lieu of filing Form 3160-5, after initial production*).

8. Ancillary Facilities:

Please see the Natural Buttes SOP.

9. Well Site Layout: (See Location Layout Diagram)

The attached Location Layout Diagram describes drill pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s), and surface material stockpile(s).

Please see the attached diagram to describe rig orientation, parking areas, and access roads.

Culverts will be installed where needed.

A run off diversion for drainage will be constructed where needed.

The reserve pit will be lined. When the reserve pit is closed the pit liner will be buried below plow depth.

Location size may change prior to the drilling of the well due to the current rig availability. If the proposed location is not large enough to accommodate the drilling rig. The location will be re-surveyed and a form 3160-5 will be submitted.

10. Plans for Reclamation of the Surface:

Please see the Natural Buttes SOP.

11. Surface Ownership:

The well pad and access road are located on lands owned by:

Ute Indian Tribe
P.O. Box 70
Fort Duchesne, Utah 84026
(435) 722-5141

12. Other Information:

A Class III Archaeological Survey Report has been conducted for this location and submitted to the Ute Indian Tribe prior to the on-site inspection.

This location is not within 460' from the boundary of the Natural Buttes Unit, nor is it within 460' of any non-committed tract lying within boundaries of the unit.

13. Lessee's or Operator's Representative & Certification:

Sheila Upchego
Senior Land Admin Specialist
Kerr-McGee Oil & Gas Onshore LP
1368 South 1200 East
Vernal, UT 84078
(435) 781-7024

Randy Bayne
Drilling Manager
Kerr-McGee Oil & Gas Onshore LP
1368 South 1200 East
Vernal, UT 84078
(435) 781-7018

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under the terms and conditions of the lease for the operations conducted upon leased lands.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Bureau of Indian Affairs Nationwide Bond #RLB0005239, Bureau of Land Management Nationwide Bond #WYB000291 and State of Utah Bond #RLB0005237.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed by the Operator, its contractors, and subcontractors in conformity with this plan and the terms and conditions under which it is approved.


Sheila Upchego

4/18/2007

Date



KERR-McGEE OIL & GAS ONSHORE LP **DRILLING PROGRAM**

CASING PROGRAM

	SIZE	INTERVAL	WT.	GR	GV/LG	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'				2270	1370	254000
SURFACE	9-5/8"	0 to 2100	32.30	H-40	STC	0.57*****	1.39	3.59
	9-5/8"	2100 to 2500	36.00	J-55	STC	1.11*****	1.73	7.98
PRODUCTION	4-1/2"	0 to 10130	11.60	I-80	LTC	1.95	1.02	1.96

- 1) Max Anticipated Surf. Press.(MASP) (Surface Casing) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point)
- 2) MASP (Prod Casing) = Pore Pressure at TD - (.22 psi/ft-partial evac gradient x TD)
- (Burst Assumptions: TD = 11.8 ppg) .22 psi/ft = gradient for partially evac wellbore
- (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)
- MASP 3987 psi
- ***** Burst SF is low but csg is stronger than formation at 2500 feet
- ***** EMW @ 2500 for 2270# is 17.5 ppg or 0.9 psi/ft

CEMENT PROGRAM

		ST. OF HOLE	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE Option 1	LEAD	500	Premium cmt + 2% CaCl + .25 pps floccle	215	60%	15.60	1.18
	TOP OUT CMT (1)	250	20 gals sodium silicate + Premium cmt + 2% CaCl + .25 pps floccle	100		15.60	1.18
	TOP OUT CMT (2)	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
SURFACE Option 2	LEAD	2000	NOTE: If well will circulate water to surface, option 2 will be utilized Prem cmt + 16% Gel + 10 pps gilsonite +.25 pps Floccle + 3% salt BWOC	230	35%	11.00	3.82
	TAIL	500	Premium cmt + 2% CaCl + .25 pps floccle	180	35%	15.60	1.18
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
PRODUCTION	LEAD	4,500'	Premium Lite II + 3% KCl + 0.25 pps celloflake + 5 pps gilsonite + 10% gel + 0.5% extender	490	60%	11.00	3.38
	TAIL	5,630'	50/50 Poz/G + 10% salt + 2% gel +.1% R-3	1570	60%	14.30	1.31

*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe.
PRODUCTION	Float shoe, 1 jt, float collar. Centralize first 3 joints & every third joint to top of tail cement with bow spring centralizers.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

SCOPE: 11" SM with one annular and 2 rams. Test to 5,000 psi (annular to 2,500 psi) prior to drilling out. Record on chart recorder &

four sheet. Function test rams on each trip. Maintain safety valve & inside BOP on rig floor at all times. Kelly to be equipped with upper & lower kelly valves.

Drop Totco surveys every 2000'. Maximum allowable hole angle is 5 degrees.

Most rigs have PVT Systems for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER:

Brad Laney

DATE:

DRILLING SUPERINTENDENT:

Randy Bayne

DATE:

NBU921-16P DHD

NBU 921-16P
SE/SE SEC. 16, T9S, R21E
UINTAH COUNTY, UTAH
ML-3282-A

ONSHORE ORDER NO. 1

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. **Existing Roads:**

Refer to the attached location directions.

Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

2. **Planned Access Roads:**

Please see the Natural Buttes Unit Standard Operating Procedure (SOP).

Approximately 70' +/- of new access road. Please refer to the attached Topo Map B.

3. **Location of Existing Wells Within a 1-Mile Radius:**

Please refer to Topo Map C.

4. **Location of Existing & Proposed Facilities:**

Please see the Natural Buttes Unit SOP.

Approximately 2830' +/- of 4" pipeline is proposed from the location to an existing pipeline.

All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded. The requested color is Carlsbad Canyon Brown (2.5Y 6/2), a non-reflective earthtone.

5. **Location and Type of Water Supply:**

Please see the Natural Buttes SOP.

6. **Source of Construction Materials:**

Please see the Natural Buttes SOP.

7. **Methods of Handling Waste Materials:**

Please see the Natural Buttes SOP.

Any produced water from the proposed well will be contained in a water tank and will then be hauled by truck to one of the pre-approved disposal sites: RNI, Sec. 5, T9S, R22E, NBU #159, Sec. 35, T9S R21E, Ace Oilfield, Sec. 2, T6S, R20E, MC&MC, Sec. 12, T6S, R19E (*Request is in lieu of filing Form 3160-5, after initial production*).

8. **Ancillary Facilities:**

Please see the Natural Buttes SOP.

9. **Well Site Layout:** (See Location Layout Diagram)

The attached Location Layout Diagram describes drill pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s), and surface material stockpile(s).

Please see the attached diagram to describe rig orientation, parking areas, and access roads.

Culverts will be installed where needed.

A run off diversion for drainage will be constructed where needed.

The reserve pit will be lined. When the reserve pit is closed the pit liner will be buried below plow depth.

Location size may change prior to the drilling of the well due to the current rig availability. If the proposed location is not large enough to accommodate the drilling rig. The location will be re-surveyed and a form 3160-5 will be submitted.

10. **Plans for Reclamation of the Surface:**

Please see the Natural Buttes SOP.

11. **Surface Ownership:**

The well pad and access road are located on lands owned by:

Ute Indian Tribe
P.O. Box 70
Fort Duchesne, Utah 84026
(435) 722-5141

12. **Other Information:**

A Class III Archaeological Survey Report has been conducted for this location and submitted to the Ute Indian Tribe prior to the on-site inspection.

This location is not within 460' from the boundary of the Natural Buttes Unit, nor is it within 460' of any non-committed tract lying within boundaries of the unit.

13. Lessee's or Operator's Representative & Certification:

Sheila Upchego
Senior Land Admin Specialist
Kerr-McGee Oil & Gas Onshore LP
1368 South 1200 East
Vernal, UT 84078
(435) 781-7024

Randy Bayne
Drilling Manager
Kerr-McGee Oil & Gas Onshore LP
1368 South 1200 East
Vernal, UT 84078
(435) 781-7018

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under the terms and conditions of the lease for the operations conducted upon leased lands.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Bureau of Indian Affairs Nationwide Bond #RLB0005239, Bureau of Land Management Nationwide Bond #WYB000291 and State of Utah Bond #RLB0005237.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed by the Operator, its contractors, and subcontractors in conformity with this plan and the terms and conditions under which it is approved.


Sheila Upchego

6/21/2007

Date

Kerr-McGee Oil & Gas Onshore LP

NBU #921-16P

SECTION 16, T9S, R21E, S.L.B.&M.

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; TURN LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 1.8 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY, THEN SOUTHEASTERLY, THEN NORTHEASTERLY DIRECTION APPROXIMATELY 3.8 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN RIGHT AND PROCEED IN A SOUTHEASTERLY, THEN EASTERLY DIRECTION APPROXIMATELY 1.8 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN RIGHT AND PROCEED IN A SOUTHEASTERLY DIRECTION APPROXIMATELY 2.9 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN LEFT AND PROCEED IN A SOUTHEASTERLY, THEN EASTERLY DIRECTION APPROXIMATELY 1.2 MILES TO THE BEGINNING OF THE PROPOSED ACCESS TO THE SOUTHWEST; FOLLOW ROAD FLAGS IN A SOUTHWESTERLY DIRECTION APPROXIMATELY 70' TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 42.5 MILES.

Kerr-McGee Oil & Gas Onshore LP

NBU #921-16P

LOCATED IN UINTAH COUNTY, UTAH
SECTION 16, T9S, R21E, S.L.B.&M.




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: EASTERLY



PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: WESTERLY



- Since 1964 -

UELS

Uintah Engineering & Land Surveying

85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS

01 30 07
MONTH DAY YEAR

PHOTO

TAKEN BY: D.K.

DRAWN BY: C.P.

REVISED: 04-24-07

Kerr-McGee Oil & Gas Onshore LP

LOCATION LAYOUT FOR

NBU #921-16P

SECTION 16, T9S, R21E, S.L.B.&M.

962' FSL 491' FEL

Existing Road

Proposed Access Road

Approx.
Toe of
Fill Slope

F-1.9'
El. 808.5'

F-2.6'
El. 807.8'

SCALE: 1" = 50'
DATE: 04-30-07
Drawn By: C.H.

NOTE:

Flare Pit is to be located
a min. of 100' from the
Well Head.

Reserve Pit Backfill
& Spoils Stockpile

El. 812.0'
C-11.6
(btm. pit) |

FLARE (PI)

Pit Topsoil

Blooië Line

RESERVE PITS
(10' Deep)

**Total Pit Capacity
W/2' of Freeboard
= 9,850 Bbls. ±
Total Pit Volume
= 2,780 Cu. Yds.**

15' WIDE BENCH/DIKE

Approx.
Top of
Cut Slope

El. 808.2'
C-7.8'
(btm. pit)

D C-1.4'
El. 811.8'

5
C-1.2'
El. 811.6

C-1.9'
El. 812.3'

LIGHT PLANT

BOILER

PUMP HOUSE

TRASH

4' 170'

PROPANE STORAGE

Sta. 0+50

F-3.1'
El. 807.3'

Topsoil Stockpile

Sta. 1+70

C-4.3'
El. 814.7'

$F-4.0'$
El. 806.4'

NOTES:

Elev. Ungraded Ground At Loc. Stake = 4812.3'
FINISHED GRADE ELEV. AT LOC. STAKE = 4810.4'

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

FIGURE #1

Kerr-McGee Oil & Gas Onshore LP

FIGURE #2

TYPICAL CROSS SECTIONS FOR

NBU #921-16P


SECTION 16, T9S, R21E, S.L.B.&M.

962' FSL 491' FEL

1" = 20'
X-Section
Scale
1" = 50'

DATE: 04-30-07
Drawn By: C.H.

Slope = 1 1/2:1
(Typ.)



NOTE:

Topsoil should not be Stripped Below Finished Grade on Substructure Area.

* NOTE:


FILL QUANTITY INCLUDES 5% FOR COMPACTION

APPROXIMATE YARDAGES

CUT	
(6") Topsoil Stripping	= 1,680 Cu. Yds.
Remaining Location	= 4,470 Cu. Yds.
TOTAL CUT	= 6,150 CU.YDS.
FILL	= 3,080 CU.YDS.

EXCESS MATERIAL	= 3,070 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	= 3,070 Cu. Yds.
EXCESS UNBALANCE (After Interim Rehabilitation)	= 0 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017



LEGEND:

○ PROPOSED LOCATION

N

Kerr-McGee Oil & Gas Onshore LP

NBU #921-16P

SECTION 16, T9S, R21E, S.L.B.&M.

962' FSL 491' FEL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP


01 30 07
 MONTH DAY YEAR

SCALE: 1:100,000

DRAWN BY: C.P.

REVISED: 04-24-07


A
TOPO



LEGEND:

Kerr-McGee Oil & Gas Onshore LP





APPROXIMATE TOTAL PIPELINE DISTANCE = 2,830' +/-

LEGEND:

- PROPOSED ACCESS ROAD
- EXISTING PIPELINE
- - - PROPOSED PIPELINE



Kerr-McGee Oil & Gas Onshore LP

NBU #921-16P

SECTION 16, T9S, R21E, S.L.B.&M.

962' FSL 491' FEL



Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP

01	30	07
MONTH	DAY	YEAR

SCALE: 1" = 1000'

DRAWN BY: C.P.

REVISED: 04-24-07



Kerr-McGee Oil & Gas Onshore LP

NBU #921-16P
PIPELINE ALIGNMENT

LOCATED IN UTAH COUNTY, UTAH
SECTION 16, T9S, R21E, S.L.B.&M.




PHOTO: VIEW FROM TIE-IN POINT

CAMERA ANGLE: NORTHERLY




PHOTO: VIEW OF PIPELINE ALIGNMENT

CAMERA ANGLE: NORTHWESTERLY



- Since 1964 -

UELS Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com

PIPELINE PHOTOS

01 30 07
MONTH DAY YEAR

PHOTO

TAKEN BY: L.K.

DRAWN BY: C.P.

REVISED: 04-24-07

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 04/23/2007

API NO. ASSIGNED: 43-047-39254

WELL NAME: NBU 921-16P

OPERATOR: KERR-MCGEE OIL & GAS (N2995)

PHONE NUMBER: 435-781-7024

CONTACT: SHEILA UPCHEGO

PROPOSED LOCATION:

SESE 16 090S 210E

SURFACE: 0962 FSL 0491 FEL

BOTTOM: 0962 FSL 0491 FEL

COUNTY: Uintah

LATITUDE: 40.03146 LONGITUDE: -109.5435

UTM SURF EASTINGS: 623861 NORTHINGS: 4432048

FIELD NAME: NATURAL BUTTES (630)

INSPECT LOCATN BY: / /		
Tech Review	Initials	Date
Engineering	DRD	6/30/08
Geology		
Surface		

LEASE TYPE: 3 - State

LEASE NUMBER: ML-3282-A

SURFACE OWNER: 2 - Indian

PROPOSED FORMATION: WSMVD

COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:

☒ Plat
☒ Bond: Fed[] Ind[] Sta[] Fee[]
(No. 22013542)
☒ Potash (Y/N)
☒ Oil Shale 190-5 (B) or 190-3 or 190-13
☒ Water Permit
(No. 43-8496)
☒ RDCC Review (Y/N)
(Date:)
☒ Fee Surf Agreement (Y/N)
☒ Intent to Commingle (Y/N)

LOCATION AND SITING:

___ R649-2-3.

Unit: NATURAL BUTTES

___ R649-3-2. General

Siting: 460' From Qtr/Qtr & 920' Between Wells

___ R649-3-3. Exception

☒ Drilling Unit

Board Cause No: 173-14

Eff Date: 12-2-99

Siting: 460' W Wbary 914m. Tract

___ R649-3-11. Directional Drill

COMMENTS: See Separate file

STIPULATIONS: 1- Federal Approval


2- OIL SHALE

3- STATEMENT OF BASIS

4- Surface Csg Cont Step

NATURAL BUTTES FIELD NATURAL BUTTES UNIT

CAUSE: 173-14 / 12-2-1999



OPERATOR: KERR MCGEE O&G (N2995)

SEC: 16 T.9S R. 21E

FIELD: NATURAL BUTTES (630)

COUNTY: UINTAH

CAUSE: 173-14 / 12-2-1999

Field Status
 ABANDONED
 ACTIVE
 COMBINED
 INACTIVE
 PROPOSED
 STORAGE
 TERMINATED

Unit Status
 EXPLORATORY
 GAS STORAGE
 NF PP OIL
 NF SECONDARY
 PENDING
 PI OIL
 PP GAS
 PP GEOTHERML
 PP OIL
 SECONDARY
 TERMINATED

Wells Status

GAS INJECTION
 GAS STORAGE
 LOCATION ABANDONED
 NEW LOCATION
 PLUGGED & ABANDONED
 PRODUCING GAS
 PRODUCING OIL
 SHUT-IN GAS
 SHUT-IN OIL
 TEMP. ABANDONED
 TEST WELL
 WATER INJECTION
 WATER SUPPLY
 WATER DISPOSAL
 DRILLING



PREPARED BY: DIANA MASON
 DATE: 26-JUNE-2007

Application for Permit to Drill

Statement of Basis

8/9/2007

Utah Division of Oil, Gas and Mining

Page 1

APD No	API WellNo	Status	Well Type	Surf Ownr	CBM		
497	43-047-39254-00-00		GW	I	No		
Operator	KERR-MCGEE OIL & GAS ONSHORE, LP		Surface Owner-APD				
Well Name	NBU 921-16P	Unit	NATURAL BUTTES				
Field	NATURAL BUTTES	Type of Work					
Location	SESE 16 9S 21E S 962 FSL 491 FEL GPS Coord (UTM) 623861E 4432048N						

Geologic Statement of Basis

Kerr McGee proposes to set 2,500' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 400'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of Section 16. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. The proposed surface casing and cement should adequately protect ground water in this area.

Brad Hill

8/9/2007

APD Evaluator

Date / Time

Surface Statement of Basis

The surface rights at the proposed location are owned by the Ute Indian Tribe. The operator is responsible for obtaining all required permits and rights-of-way prior to making any surface disturbance or drilling the well.

Brad Hill

8/9/2007

Onsite Evaluator

Date / Time

Conditions of Approval / Application for Permit to Drill

Category	Condition
	None.

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator KERR-MCGEE OIL & GAS ONSHORE, LP
Well Name NBU 921-16P
API Number 43-047-39254-0 **APD No** 497 **Field/Unit** NATURAL BUTTES
Location: 1/4,1/4 SESE **Sec** 16 **Tw** 9S **Rng** 21E 962 FSL 491 FEL
GPS Coord (UTM) **Surface Owner**

Participants

Regional/Local Setting & Topography

Surface Use Plan

Current Surface Use

New Road

Miles	Well Pad Width	Length	Src Const Material	Surface Formation
--------------	---------------------------	---------------	---------------------------	--------------------------

Ancillary Facilities

Waste Management Plan Adequate?

Environmental Parameters

Affected Floodplains and/or Wetland

Flora / Fauna

Soil Type and Characteristics

Erosion Issues

Sedimentation Issues

Site Stability Issues

Drainage Diversion Required

Berm Required?

Erosion Sedimentation Control Required?

Paleo Survey Run?	Paleo Potential Observed?	Cultural Survey Run?	Cultural Resources?
--------------------------	----------------------------------	-----------------------------	----------------------------

Reserve Pit

Site-Specific Factors**Site Ranking**


Distance to Groundwater (feet)
Distance to Surface Water (feet)
Dist. Nearest Municipal Well (ft)
Distance to Other Wells (feet)
Native Soil Type
Fluid Type
Drill Cuttings
Annual Precipitation (inches)
Affected Populations
Presence Nearby Utility Conduits

Final Score**Sensitivity Level****Characteristics / Requirements****Closed Loop Mud Required?****Liner Required?****Liner Thickness****Pit Underlayment Required?****Other Observations / Comments**

Brad Hill
Evaluator

8/9/2007
Date / Time

Casing Schematic



Well name:	2008-06 Kerr McGee NBU 921-16P (rev/2007-04)	
Operator:	Kerr McGee Oil & Gas Onshore L.P.	
String type:	Surface	Project ID: 43-047-39254
Location:	Uintah County, Utah	

Design parameters:
Collapse

Mud weight: 8.300 ppg
Design is based on evacuated pipe.

Minimum design factors:
Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 110 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,400 ft

Cement top: 780 ft

Burst

Max anticipated surface pressure: 2,200 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 2,500 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on buoyed weight.
Neutral point: 2,193 ft

Non-directional string.
Re subsequent strings:

Next setting depth: 10,130 ft
Next mud weight: 11.800 ppg
Next setting BHP: 6,210 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 2,500 ft
Injection pressure: 2,500 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	2500	9.625	36.00	J-55	ST&C	2500	2500	8.796	1085.1

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	1078	2020	1.874	2500	3520	1.41	79	394	4.99 J

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Minerals

Phone: (801) 538-5357
FAX: (801) 359-3940

Date: June 27, 2008
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 2500 ft, a mud weight of 8.3 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Well name:	2008-06 Kerr McGee NBU 921-16P (rev/2007-04)	
Operator:	Kerr McGee Oil & Gas Onshore L.P.	
String type:	Production	Project ID: 43-047-39254
Location:	Uintah County, Utah	

Design parameters:
Collapse

Mud weight: 11.800 ppg
Design is based on evacuated pipe.

Minimum design factors:
Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 217 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,500 ft

Cement top: Surface

Burst

Max anticipated surface pressure: 3,981 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 6,210 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Non-directional string.

Tension is based on buoyed weight.
Neutral point: 8,343 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	10130	4.5	11.60	I-80	LT&C	10130	10130	3.875	884

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	6210	6360	1.024	6210	7780	1.25	97	212	2.19 J

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Minerals

Phone: (801) 538-5357
FAX: (801) 359-3940

Date: June 27, 2008
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 10130 ft, a mud weight of 11.8 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

BOPE REVIEW

Kerr-McGee NBU 921-16P API 43-047-39254

INPUT

Well Name

Kerr-McGee NBU 921-16P API 43-047-39254

Casing Size (")

String 1	String 2		
9 5/8	4 1/2		
2500	10130		
40	2900		
8.3	11.8		
500	5000		
3520	10690		
6281	11.9 ppg		

Setting Depth (TVD)

Previous Shoe Setting Depth (TVD)

Max Mud Weight (ppg)

BOPE Proposed (psi)

Casing Internal Yield (psi)

Operators Max Anticipated Pressure (psi)

Calculations

String 1 9 5/8 "

Max BHP [psi]	.052*Setting Depth*MW =	1079	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) [psi]	Max BHP-(0.12*Setting Depth) =	779	NO Air Drill to surface shoe
MASP (Gas/Mud) [psi]	Max BHP-(0.22*Setting Depth) =	529	NO
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth) =	529	NO - no expected pressure
Required Casing/BOPE Test Pressure		2464 psi	
*Max Pressure Allowed @ Previous Casing Shoe =		40 psi	

Calculations

String 2 4 1/2 "

Max BHP [psi]	.052*Setting Depth*MW =	6216	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) [psi]	Max BHP-(0.12*Setting Depth) =	5000	NO
MASP (Gas/Mud) [psi]	Max BHP-(0.22*Setting Depth) =	3987	YES ✓
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth) =	4427	NO Penetration
Required Casing/BOPE Test Pressure		5000 psi	
*Max Pressure Allowed @ Previous Casing Shoe =		2900 psi	*Assumes 1psi/ft frac gradient

United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office

P.O. Box 45155

Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:

3160

(UT-922)

April 25, 2007

Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2007 Plan of Development Natural Buttes Unit
Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2007 within the Natural Buttes Unit, Uintah County, Utah.

API#	WELL NAME	LOCATION
------	-----------	----------

(Proposed PZ Wasatch/MesaVerde)

43-047-39237	NBU 921-8B	Sec 08 T09S R21E 0528 FNL 2080 FEL
43-047-39238	NBU 921-8H	Sec 08 T09S R21E 1870 FNL 0837 FEL
43-047-39239	NBU 921-8P	Sec 08 T09S R21E 0533 FSL 0578 FEL
43-047-39240	NBU 921-9K	Sec 09 T09S R21E 2633 FSL 2383 FWL
43-047-39241	NBU 921-9C	Sec 09 T09S R21E 0896 FNL 1569 FWL
43-047-39254	NBU 921-16P	Sec 16 T09S R21E 0537 FSL 0610 FEL
43-047-39255	NBU 921-18D	Sec 18 T09S R21E 0550 FNL 0827 FWL
43-047-39256	NBU 921-21L	Sec 21 T09S R21E 1785 FSL 0797 FWL
43-047-39242	NBU 921-10H	Sec 10 T09S R21E 1472 FNL 1104 FEL
43-047-39243	NBU 921-13H	Sec 13 T09S R21E 2323 FNL 0531 FEL
43-047-39244	NBU 921-13E	Sec 13 T09S R21E 1818 FNL 0851 FWL
43-047-39245	NBU 921-13LT	Sec 13 T09S R21E 1465 FSL 0792 FWL
43-047-39246	NBU 921-14B	Sec 14 T09S R21E 0822 FNL 1764 FEL
43-047-39247	NBU 921-14D	Sec 14 T09S R21E 0465 FNL 0542 FWL
43-047-39248	NBU 921-14P	Sec 14 T09S R21E 0878 FSL 1163 FEL
43-047-39249	NBU 921-14A	Sec 14 T09S R21E 1239 FNL 0883 FEL
43-047-39250	NBU 921-14G	Sec 14 T09S R21E 2319 FNL 1996 FEL
43-047-39251	NBU 921-14H	Sec 14 T09S R21E 2088 FNL 0422 FEL
43-047-39252	NBU 921-15E	Sec 15 T09S R21E 2184 FNL 0636 FWL
43-047-39253	NBU 921-15L	Sec 15 T09S R21E 2015 FSL 0713 FWL

We have no objections to permitting the wells so long as the unit operator receives an exception to the locating and siting requirements of the State of Utah (R649-3-2).

/s/ Michael L. Coulthard

bcc: File - Natural Buttes Unit
Division of Oil Gas and Mining
Central Files
Agr. Sec. Chron
Fluid Chron

MCoulthard:mc:4-25-07

United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:
3160
(UT-922)

June 28, 2007

Memorandum

To: Assistant District Manager Minerals, Vernal District
From: Michael Coulthard, Petroleum Engineer
Subject: 2007 Plan of Development Natural Buttes Unit
Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following well's location has changed from that identified in our memo of April 25, 2007. It is planned for calendar year 2007 within the Natural Buttes Unit, Uintah County, Utah.

API#	WELL NAME	LOCATION
------	-----------	----------

(Proposed PZ Wasatch/MesaVerde)

43-047-39254 NBU 921-16P Sec 16 T09S R21E 0962 FSL 0491 FEL

This office has no objection to permitting the wells at this time.

/s/ Michael L. Coulthard

bcc: File - Natural Buttes Unit
Division of Oil Gas and Mining
Central Files
Agr. Sec. Chron
Fluid Chron

MCoulthard:mc:6-28-07

Helen Sadik-Macdonald - Surface Casing changes

From: "Laney, Brad"
To:
Date: 09/07/2007 3:26 PM
Subject: Surface Casing changes
CC: "Upchego, Sheila" , "Worthen, Rebecca"

Helen,

The following wells will have 36# casing run in them for the entire surface casing interval.

NBU 921-16P
NBU 921-16J
NBU 921-16HT
NBU 921-16MT
NBU 921-25NT
NBU 921-34MT

Anadarko is currently in the process of converting all future wells to a 36# surface casing string but we will continue to utilize our existing inventory of 32.3# until sometime in October. All future permits will reflect the changes to the surface casing. If you need any additional paperwork or have any questions, let me know.

Thanks again
Brad

Anadarko Confidentiality Notice: This electronic transmission and any attached documents or other writings are intended only for the person or entity to which it is addressed and may contain information that is privileged, confidential or otherwise protected from disclosure. If you have received this communication in error, please immediately notify sender by return e-mail and destroy the communication. Any disclosure, copying, distribution or the taking of any action concerning the contents of this communication or any attachments by anyone other than the named recipient is strictly prohibited.

Helen Sadik-Macdonald - RE: Tribal 822-31O, NBU 921-16P

From: "Laney, Brad"
To: "Helen Sadik-Macdonald"
Date: 06/20/2008 3:59 PM
Subject: RE: Tribal 822-31O, NBU 921-16P
CC: "Dustin Doucet"

Dustin,

Sorry for the delayed response on these two APD issues.

First, I will address the Tribal 822-31O surface casing issue. As you are aware, as part of our field standard operating procedure (SOP) we have switched all of our surface casing to the requested 36# J55 for the entire field so the 822-31O surface casing string will utilize the stronger casing as requested by UDOGM.

Secondly, both the Tribal 822-31O and the NBU 921-16P will be drilled to $\pm 10150'$. Helen has stated that UDOGM does not make exceptions to pipe which does not meet the 1.125 collapse and 1.00 burst, and, therefore, is requesting Anadarko to run P110 below 9200'. It is Anadarko's Natural Buttes SOP to run I80 casing to depths of $\pm 10200'$ even though the collapse and burst may not meet your requirements. Anadarko operates in this manner for the following reasons.

1. Standard running procedures include filling the pipe at the surface casing shoe and at least one additional time (usually at the top of the Mesaverde formation or $\pm 2000'$ from TD) before reaching TD. This ensures the pipe to be over half full with drilling mud before reaching TD which prevents collapse from occurring.
2. Our standard cementing procedure brings cement all the way back to surface and once it sets, provides support around the casing for burst and collapse. After the cement hardens, the casing will only collapse if there is a plastic formation like a salt. In Natural Buttes, no plastic formations are found. Before stimulating the well for the initial completion, the wellhead and casing are pressure tested for burst. The stimulating pressures are consistently greater than 5000 psi and, to my knowledge, only one time has the casing ever failed due to burst. It was later determined that the casing failed due to a quality control issue during the manufacturing process.

Anadarko has set I80 production casing many times below 9200' in comparable wells with comparable pressures. In fact, earlier this month we set 10,300' of I80 in the NBU 921-9C well bore. Therefore, I am requesting approval of the Tribal 822-31O and NBU 921-16P proposed casing designs.

If you need further detail, have any questions, or would like this request to be submitted on a sundry, please give me a call.

Thanks



Brad Laney Drilling Engineer, Uinta Basin
Anadarko Petroleum Corp., 1368 South 1200 East, Vernal, UT 84078
office: 435.781.7031
cell: 435.828.5469 email: brad.laney@anadarko.com

From: Helen Sadik-Macdonald [mailto:hmacdonald@utah.gov]
Sent: Wednesday, April 23, 2008 4:53 PM
To: Laney, Brad
Cc: Dustin Doucet
Subject: Tribal 822-310, NBU 921-16P

Brad,
Congratulation to Anadarko/Kerr-McGee on your awards. Hope your return to Vernal was uneventful.

Comments on the above-cited wells:

These two wells are proposed at 10180' and 10130' TD, respectively. We run our analysis of pipe grade with design factors of 1.125 collapse and 1.00 burst on evacuated pipe. We do not make exceptions to pipe meeting design factors on surface and production strings for several reasons. Chief among those reasons is to provide adequate protection of fresh ground water resources (surface casing) and to prevent collapse and corrosion issues over time in the production string.

We occasionally will apply an annular backup to intermediate casing if it does not quite meet design criteria. We do this because it not only is reinforced by cement, but the production string will add an additional layer of protection.

Production casing is affected by perfs, formation fluids, stimulating fluids, lifting mechanisms, etc. in addition to formation pressure. Therefore, meeting design factors of 1.125-collapse and 1.00-burst is the Division's minimum standard to delay wear and tear.

Both of these wells will pass collapse if 11.6# P-110 is set below 9200 feet. Some other design of your choosing is acceptable if it meets design criteria. Additionally, the Tribal 822-310 needs the surface string upgraded to 36# J-55. I do not have an e-mail from you stating this change. I do have said e-mail for the 16P. Thank you. hsm

*Helen Sadik-Macdonald, CPG, PG
Petroleum Engineering Services
Utah Div. of Oil, Gas & Mining
PO Box 145801
Salt Lake City, UT 84114-5801*

801/538-5357 Desk
801/359-3940 Fax

Anadarko Confidentiality Notice: This electronic transmission and any attached documents or other writings are intended only for the person or entity to which it is addressed and may contain information that is privileged, confidential or otherwise protected from disclosure. If you have received this communication in error, please immediately notify sender by return e-mail and destroy the communication. Any disclosure, copying, distribution or the taking of any action concerning the contents of this communication or any attachments by anyone other than the named recipient is strictly prohibited.



JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

July 7, 2008

Kerr-McGee Oil & Gas Onshore LP
1368 S 1200 E
Vernal, UT 84078

Re: NBU 921-16P Well, 962' FSL, 491' FEL, SE SE, Sec. 16, T. 9 South, R. 21 East,
Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-39254.

Sincerely,

Gil Hunt
Associate Director

pab
Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal Office
SITLA

Operator: Kerr-McGee Oil & Gas Onshore LP

Well Name & Number NBU 921-16P

API Number: 43-047-39254

Lease: ML-3282-A

Location: SE SE Sec. 16 T. 9 South R. 21 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

The operator is required to notify the Division of Oil, Gas and Mining of the following action during drilling of this well:

- 24 hours prior to cementing or testing casing – contact Dan Jarvis
- 24 hours prior to testing blowout prevention equipment – contact Dan Jarvis
- 24 hours prior to spudding the well – contact Carol Daniels
- Within 24 hours of any emergency changes made to the approved drilling program – contact Dustin Doucet
- Prior to commencing operations to plug and abandon the well – contact Dan Jarvis

The operator is required to get approval from the Division of Oil, Gas and Mining before performing any of the following actions during the drilling of this well:

- Plugging and abandonment or significant plug back of this well – contact Dustin Doucet
- Any changes to the approved drilling plan – contact Dustin Doucet

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at: (801) 538-5338 office (801) 942-0871 home
- Carol Daniels at: (801) 538-5284 office
- Dustin Doucet at: (801) 538-5281 office (801) 733-0983 home

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.
5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)
6. In accordance with Order in Cause No. 190-5(b) dated October 28, 1982, the Operator shall comply with requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operator shall ensure that the surface and/or production casing is properly cemented over the entire oil shale interval as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the Division.
7. Surface casing shall be cemented to the surface.
8. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-3282-A			
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE			
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES			
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 921-16P			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0962 FSL 0491 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESE Section: 16 Township: 09.0S Range: 21.0E Meridian: S		9. API NUMBER: 43047392540000			
PHONE NUMBER: 720 929-6007 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES			
COUNTY: UTAH		STATE: UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION	TYPE OF ACTION				
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 6/26/2009 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER:
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER:			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Kerr-McGee Oil & Gas Onshore, L.P. (Kerr-McGee) respectfully requests an extension to this APD for the maximum time allowed. Please contact the undersigned with any questions and/or comments. Thank you.					
<div style="text-align: right;"> Approved by the Utah Division of Oil, Gas and Mining </div>		Date: June 23, 2009 By:			
NAME (PLEASE PRINT) Danielle Piernot		PHONE NUMBER 720 929-6156			
SIGNATURE N/A		TITLE Regulatory Analyst			
DATE 6/23/2009					



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources
Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047392540000

API: 43047392540000

Well Name: NBU 921-16P

Location: 0962 FSL 0491 FEL QTR SESE SEC 16 TWNP 090S RNG 210E MER S

Company Permit Issued to: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Date Original Permit Issued: 7/7/2008

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☐ Yes ☒ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

**Approved by the
Utah Division of
Oil, Gas and Mining**

Signature: Danielle Piernot

Date: 6/23/2009

Title: Regulatory Analyst **Representing:** KERR-MCGEE OIL & GAS ONSHORE, L.P.

Date: June 23, 2009

By: 

RECEIVED June 23, 2009

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9																														
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-3282-A																														
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE																														
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES																														
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 921-16P																														
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0962 FSL 0491 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESE Section: 16 Township: 09.0S Range: 21.0E Meridian: S		9. API NUMBER: 43047392540000																														
PHONE NUMBER: 720 929-6007 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES																														
COUNTY: UTAH		STATE: UTAH																														
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA																																
TYPE OF SUBMISSION	TYPE OF ACTION																															
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 6/26/2009 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<table style="width: 100%; border: none;"> <tr> <td><input type="checkbox"/> ACIDIZE</td> <td><input type="checkbox"/> ALTER CASING</td> <td><input type="checkbox"/> CASING REPAIR</td> </tr> <tr> <td><input type="checkbox"/> CHANGE TO PREVIOUS PLANS</td> <td><input type="checkbox"/> CHANGE TUBING</td> <td><input type="checkbox"/> CHANGE WELL NAME</td> </tr> <tr> <td><input type="checkbox"/> CHANGE WELL STATUS</td> <td><input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS</td> <td><input type="checkbox"/> CONVERT WELL TYPE</td> </tr> <tr> <td><input type="checkbox"/> DEEPEN</td> <td><input type="checkbox"/> FRACTURE TREAT</td> <td><input type="checkbox"/> NEW CONSTRUCTION</td> </tr> <tr> <td><input type="checkbox"/> OPERATOR CHANGE</td> <td><input type="checkbox"/> PLUG AND ABANDON</td> <td><input type="checkbox"/> PLUG BACK</td> </tr> <tr> <td><input type="checkbox"/> PRODUCTION START OR RESUME</td> <td><input type="checkbox"/> RECLAMATION OF WELL SITE</td> <td><input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION</td> </tr> <tr> <td><input type="checkbox"/> REPERFORATE CURRENT FORMATION</td> <td><input type="checkbox"/> SIDETRACK TO REPAIR WELL</td> <td><input type="checkbox"/> TEMPORARY ABANDON</td> </tr> <tr> <td><input type="checkbox"/> TUBING REPAIR</td> <td><input type="checkbox"/> VENT OR FLARE</td> <td><input type="checkbox"/> WATER DISPOSAL</td> </tr> <tr> <td><input type="checkbox"/> WATER SHUTOFF</td> <td><input type="checkbox"/> SI TA STATUS EXTENSION</td> <td><input checked="" type="checkbox"/> APD EXTENSION</td> </tr> <tr> <td><input type="checkbox"/> WILDCAT WELL DETERMINATION</td> <td><input type="checkbox"/> OTHER</td> <td>OTHER: </td> </tr> </table>		<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input checked="" type="checkbox"/> APD EXTENSION	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER:
<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR																														
<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME																														
<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE																														
<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION																														
<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK																														
<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION																														
<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON																														
<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL																														
<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input checked="" type="checkbox"/> APD EXTENSION																														
<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER:																														
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Kerr-McGee Oil & Gas Onshore, L.P. (Kerr-McGee) respectfully requests an extension to this APD for the maximum time allowed. Please contact the undersigned with any questions and/or comments. Thank you.																																
NAME (PLEASE PRINT) Danielle Piernot	PHONE NUMBER 720 929-6156	TITLE Regulatory Analyst																														
SIGNATURE N/A	DATE 6/23/2009																															

RECEIVED June 23, 2009



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047392540000

API: 43047392540000

Well Name: NBU 921-16P

Location: 0962 FSL 0491 FEL QTR SESE SEC 16 TWNP 090S RNG 210E MER S

Company Permit Issued to: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Date Original Permit Issued: 7/7/2008

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.


- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☐ Yes ☒ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

Signature: Danielle Piernot

Date: 6/23/2009

Title: Regulatory Analyst **Representing:** KERR-MCGEE OIL & GAS ONSHORE, L.P.

RECEIVED June 23, 2009

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9																														
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-3282-A																														
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE																														
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES																														
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 921-16P																														
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0962 FSL 0491 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESE Section: 16 Township: 09.0S Range: 21.0E Meridian: S		9. API NUMBER: 43047392540000																														
PHONE NUMBER: 720 929-6007 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES																														
COUNTY: UTAH		STATE: UTAH																														
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA																																
TYPE OF SUBMISSION	TYPE OF ACTION																															
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 7/7/2010 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<table style="width: 100%; border: none;"> <tr> <td><input type="checkbox"/> ACIDIZE</td> <td><input type="checkbox"/> ALTER CASING</td> <td><input type="checkbox"/> CASING REPAIR</td> </tr> <tr> <td><input type="checkbox"/> CHANGE TO PREVIOUS PLANS</td> <td><input type="checkbox"/> CHANGE TUBING</td> <td><input type="checkbox"/> CHANGE WELL NAME</td> </tr> <tr> <td><input type="checkbox"/> CHANGE WELL STATUS</td> <td><input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS</td> <td><input type="checkbox"/> CONVERT WELL TYPE</td> </tr> <tr> <td><input type="checkbox"/> DEEPEN</td> <td><input type="checkbox"/> FRACTURE TREAT</td> <td><input type="checkbox"/> NEW CONSTRUCTION</td> </tr> <tr> <td><input type="checkbox"/> OPERATOR CHANGE</td> <td><input type="checkbox"/> PLUG AND ABANDON</td> <td><input type="checkbox"/> PLUG BACK</td> </tr> <tr> <td><input type="checkbox"/> PRODUCTION START OR RESUME</td> <td><input type="checkbox"/> RECLAMATION OF WELL SITE</td> <td><input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION</td> </tr> <tr> <td><input type="checkbox"/> REPERFORATE CURRENT FORMATION</td> <td><input type="checkbox"/> SIDETRACK TO REPAIR WELL</td> <td><input type="checkbox"/> TEMPORARY ABANDON</td> </tr> <tr> <td><input type="checkbox"/> TUBING REPAIR</td> <td><input type="checkbox"/> VENT OR FLARE</td> <td><input type="checkbox"/> WATER DISPOSAL</td> </tr> <tr> <td><input type="checkbox"/> WATER SHUTOFF</td> <td><input type="checkbox"/> SI TA STATUS EXTENSION</td> <td><input checked="" type="checkbox"/> APD EXTENSION</td> </tr> <tr> <td><input type="checkbox"/> WILDCAT WELL DETERMINATION</td> <td><input type="checkbox"/> OTHER</td> <td>OTHER: _____</td> </tr> </table>		<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input checked="" type="checkbox"/> APD EXTENSION	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: _____
<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR																														
<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME																														
<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE																														
<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION																														
<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK																														
<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION																														
<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON																														
<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL																														
<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input checked="" type="checkbox"/> APD EXTENSION																														
<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: _____																														
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Kerr-McGee Oil & Gas Onshore, L.P. (Kerr-McGee) respectfully requests an extension to this APD for the maximum time allowed. Please contact the undersigned with any questions and/or comments. Thank you.																																
<div style="text-align: right;"> Approved by the Utah Division of Oil, Gas and Mining </div>		Date: July 13, 2010																														
<div style="text-align: right;"> By:  </div>																																
NAME (PLEASE PRINT) Danielle Piernot		PHONE NUMBER 720 929-6156																														
SIGNATURE N/A		TITLE Regulatory Analyst																														
		DATE 7/7/2010																														



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources
Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047392540000

API: 43047392540000

Well Name: NBU 921-16P

Location: 0962 FSL 0491 FEL QTR SESE SEC 16 TWNP 090S RNG 210E MER S

Company Permit Issued to: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Date Original Permit Issued: 7/7/2008

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☐ Yes ☒ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

**Approved by the
Utah Division of
Oil, Gas and Mining**

Signature: Danielle Piernot

Date: 7/7/2010

Title: Regulatory Analyst **Representing:** KERR-MCGEE OIL & GAS ONSHORE, L.P.

Date: July 13, 2010

By: 

RECEIVED July 07, 2010

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-3282-A			
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE			
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES			
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 921-16P			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0962 FSL 0491 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESE Section: 16 Township: 09.0S Range: 21.0E Meridian: S		9. API NUMBER: 43047392540000			
PHONE NUMBER: 720 929-6007 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES			
COUNTY: UINTAH		STATE: UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION	TYPE OF ACTION				
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 10/4/2010 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input checked="" type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input checked="" type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input checked="" type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Kerr-McGee Oil & Gas Onshore, L.P. (Kerr-McGee) respectfully requests to change the total depth (TD) to include the Blackhawk formation, which is in the Mesaverde group for this well. Please see the attached for additional details. All of the original information remains the same. Please contact the undersigned with any questions and/or comments. Thank you.					
Approved by the Utah Division of Oil, Gas and Mining		Date: <u>October 06, 2010</u> By: <u><i>Danielle Piernot</i></u>			
NAME (PLEASE PRINT) Danielle Piernot		PHONE NUMBER 720 929-6156			
SIGNATURE N/A		TITLE Regulatory Analyst			
DATE 9/28/2010					

Well name:

43047392540000 NBU 921-16Prev.

Operator: **Kerr McGee Oil & Gas Onshore L.P.**

String type: Production

Project ID:

43-047-39254-0000

Location: Uintah County, Utah

Design parameters:**Collapse**

Mud weight: 12.800 ppg

Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No

Surface temperature: 75 °F

Bottom hole temperature: 233 °F

Temperature gradient: 1.40 °F/100ft

Minimum section length: 1,500 ft

Cement top:

1,724 ft

Surf csj
@ 2800'**Burst**

Max anticipated surface pressure:

5,015 psi

Internal gradient:

0.220 psi/ft

Calculated BHP

7,494 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)

8 Round LTC: 1.80 (J)

Buttress: 1.60 (J)

Premium: 1.50 (J)

Body yield: 1.50 (B)

Non-directional string.

Tension is based on buoyed weight.

Neutral point: 9,114 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	11271	4.5	11.60	HCP-110	LT&C	11271	11271	3.875	983.6
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	7494	8650	1.154	7494	10690	1.43	106	279	2.64 J

**Approved by the
Utah Division of
Oil, Gas and Mining**

Date: October 06, 2010

By: 

Prepared by: Dustin K. Doucet
Div of Oil, Gas & Mining

Phone: (801) 538-5281
FAX: (801) 359-3940

Date: October 6, 2010
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 11271 ft, a mud weight of 12.8 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

KERR-McGEE OIL & GAS ONSHORE LP
DRILLING PROGRAM

COMPANY NAME					KERR-McGEE OIL & GAS ONSHORE LP					DATE		September 28, 2010		
WELL NAME					NBU 921-16P					TD		11,271' TVD 11,271' MD		
FIELD			Natural Buttes		COUNTY		Uintah		STATE		Utah		FINISHED ELEVATION 4,810'	
SURFACE LOCATION			SE/4 SE/4 962' FSL		491' FEL		Sec 16 T 9S		R 21E		BHL		Straight Hole	
			Latitude: 40.031494		Longitude: -109.549075						NAD 83			
OBJECTIVE ZONE(S)			Wasatch/Mesaverde											
ADDITIONAL INFO			Regulatory Agencies: BLM (MINERALS), Ute Tribe (SURFACE), UDOGM, Tri-County Health Dept.											

GEOLOGICAL				MECHANICAL		
LOGS	FORMATION	DEPTH		HOLE SIZE	CASING SIZE	MUD WEIGHT
		40'			14"	
				11"	8-5/8", 28#, IJ-55, LTC	Air mist
<p>All water flows encountered while drilling will be reported to the appropriate agencies.</p>						
	Green River @	1,644'				
	Top of Birds Nest @	1,995'				
	Mahogany @	2,350'				
	Preset f/ GL @	2,800'	MD			
<p>Note: 11" surface hole will usually be drilled ±400' below the lost circulation zone (aka bird's nest). Drilled depth may be ±200' of the estimated set depth depending on the acutal depth of the loss zone.</p>						
	Wasatch @	5,043' TVD				
<p>Mud logging program TBD Cased hole logging program from TD - surf csg</p>				7-7/8"	4-1/2" 11.6# HCP-110 or equivalent BTC/LTC csg	Water / Fresh Water Mud 8.3-12.8 ppg
	Mverde @	8,024' TVD				
	MVU21 @	8,973' TVD				
	MVU1 @	9,486' TVD				
	Sego @	10,273' TVD				
	Castlegate @	10,329' TVD				
	MN5 @	10,723' TVD				
<p>Max anticipated Mud required 12.8 ppg</p>						
	TD @	11,271'	TVD MD			



KERR-McGEE OIL & GAS ONSHORE LP DRILLING PROGRAM

CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'						
						3,390	1,880	348,000
SURFACE	8-5/8"	0 to 2,800'	28.00	IJ-55	LTC	0.67	1.43	4.39
						10,690	8,650	367,000
PRODUCTION	4-1/2"	0 to 11,271'	11.60	HCP-110	BTC	4.31	1.15	3.49

*Burst on surface casing is controlled by fracture gradient as shoe with gas gradient above.

D.F. = 1.92

1) Max Anticipated Surf. Press.(MASP) (Surface Casing) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

2) MASP (Prod Casing) = Pore Pressure at TD - (0.22 psi/ft-partial evac gradient x TD)

(Burst Assumptions: TD = 12.8 ppg)

0.22 psi/ft = gradient for partially evac wellbore

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing*Buo.Fact. of water)

MASP 4,894 psi

3) Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

(Burst Assumptions: TD = 12.8 ppg)

0.65 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing*Buo.Fact. of water)

MABHP 7,373 psi

CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE	LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80	1.15
			+ 0.25 pps flocele				
Option 1							
	TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80	1.15
			+ 2% CaCl + 0.25 pps flocele				
SURFACE		NOTE: If well will circulate water to surface, option 2 will be utilized					
Option 2	LEAD	2,300'	65/35 Poz + 6% Gel + 10 pps gilsonite	210	35%	11.00	3.82
			+ 0.25 pps Flocele + 3% salt BWOW				
	TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80	1.15
			+ 0.25 pps flocele				
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80	1.15
PRODUCTION	LEAD	4,541'	Premium Lite II + 3% KCl + 0.25 pps	340	20%	11.00	3.38
			celloflake + 5 pps gilsonite + 10% gel				
			+ 0.5% extender				
	TAIL	6,730'	50/50 Poz/G + 10% salt + 2% gel	1,410	20%	14.30	1.31
			+ 0.1% R-3				

*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe
PRODUCTION	Float shoe, 1 jt, float collar. No centralizers will be used.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys will be taken at 1,000' minimum intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER: John Huycke / Emile Goodwin

DRILLING SUPERINTENDENT: John Merkel / Lovel Young

BLM - Vernal Field Office - Notification Form

Operator KERR-McGEE OIL & GAS Rig Name/# BUCKET RIG
Submitted By ANDY LYTLE Phone Number 720.929.6100
Well Name/Number NBU 921-16P
Qtr/Qtr SESE Section 16 Township 9S Range 21E
Lease Serial Number ML-3282-A
API Number 4304739254

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time 10/11/2010 09:00 HRS AM ☐ PM ☐

Casing – Please report time casing run starts, not cementing times.

- ☒ Surface Casing
☐ Intermediate Casing
☐ Production Casing
☐ Liner
☐ Other

RECEIVED

OCT 08 2010

DIV. OF OIL, GAS & MINING

Date/Time 10/22/2010 08:00 HRS AM ☐ PM ☐

BOPE

- ☐ Initial BOPE test at surface casing point
☐ BOPE test at intermediate casing point
☐ 30 day BOPE test
☐ Other

Date/Time _____ AM ☐ PM ☐

Remarks ESTIMATED DATE AND TIME. PLEASE CONTACT KENNY GATHINGS AT

435.828.0986 OR LOVEL YOUNG AT 435.781.7051

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-3282-A
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 921-16P
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0962 FSL 0491 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESE Section: 16 Township: 09.0S Range: 21.0E Meridian: S		9. API NUMBER: 43047392540000
PHONE NUMBER: 720 929-6007 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input checked="" type="checkbox"/> SPUD REPORT Date of Spud: 10/12/2010	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. MIRU PETE MARTIN BUCKET RIG. DRILLED 20" CONDUCTOR HOLE TO 40'. RAN 14" 36.7# SCHEDULE 10 CONDUCTOR PIPE. CMT W/ 28 SX READY MIX SPUD WELL LOCATION ON OCTOBER 12, 2010 AT 09:00 HRS.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY October 21, 2010		
NAME (PLEASE PRINT) Andy Lytle	PHONE NUMBER 720 929-6100	TITLE Regulatory Analyst
SIGNATURE N/A	DATE 10/15/2010	

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: KERR McGEE OIL & GAS ONSHORE LP Operator Account Number: N 2995
Address: P.O. Box 173779
city DENVER
state CO zip 80217 Phone Number: (720) 929-6100

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304751186	NBU 922-29H1BS		NENE	29	9S	22E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
<u>B</u>	99999	<u>2980</u>	10/13/2010			<u>10/19/10</u>	
Comments: MIRU PETE MARTIN BUCKET RIG. <u>WSMVD</u> SPUD WELL LOCATION ON 10/13/2010 AT 08:00 HRS. <u>BHL = SENE</u>							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304739254	NBU 921-16P		SESE	16	9S	21E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
<u>B</u>	99999	<u>2910</u>	10/12/2010			<u>10/19/10</u>	
Comments: MIRU PETE MARTIN BUCKET RIG. <u>WSMVD</u> SPUD WELL LOCATION ON 10/12/2010 AT 09:00 HRS.							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

RECEIVED

OCT 18 2010

DIV. OF OIL, GAS & MINING

ANDY LYTLE

Name (Please Print)

Signature

REGULATORY ANALYST

Title

10/18/2010

Date

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-3282-A
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 921-16P
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0962 FSL 0491 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESE Section: 16 Township: 09.0S Range: 21.0E Meridian: S		9. API NUMBER: 43047392540000
PHONE NUMBER: 720 929-6007 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 10/19/2010	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. MIRU PROPETRO AIR RIG ON OCTOBER 16, 2010. DRILLED 11" SURFACE HOLE TO 2840'. RAN 8 5/8" 28# IJ-55 SURFACE CSG. PUMP 20 BBLS FRESH WATER. PUMP 20 BBLS GEL WATER. LEAD CEMENT W/ 220 SX CLASS G PREM @ 11.0 PPG, 3.82 YD. TAILED CEMENT W/ 200 SX CLASS G PREM LITE @ 15.8 PPG, 1.15 YD. DROP PLUG ON THE FLY, DISPLACED W/ 174.9 BBLS WATER. PARTIAL RETURNS. LIFT PRESSURE WAS 100 PSI, BUMP PLUG & HOLD 700 PSI FOR 5 MIN. FLOAT HELD. EST TOC OF TAIL @ 1490'. TOP OUT W/ 225 SX SAME CEMENT DOWN 1" BACK SIDE. WORT.		
<div style="text-align: right;"> Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY October 25, 2010 </div>		
NAME (PLEASE PRINT) Andy Lytle		PHONE NUMBER 720 929-6100
SIGNATURE N/A		TITLE Regulatory Analyst
DATE 10/20/2010		

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-3282-A
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 921-16P
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0962 FSL 0491 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESE Section: 16 Township: 09.0S Range: 21.0E Meridian: S		9. API NUMBER: 43047392540000
PHONE NUMBER: 720 929-6007 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 12/22/2010			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
 FINISHED DRILLING FROM 2840' TO 11,290' ON DECEMBER 19, 2010. RAN 4 1/2" 11.6# I-80 PRODUCTION CSG. PUMP 40 BBLS SPACER, LEAD CEMENT W/ 655 SX CLASS G PREM LITE @ 13.2 PPG, 1.69 YD. TAILED CEMENT W/ 1390 SX CLASS G 50/50 POZ MIX @ 14.3 PPG, 1.25 YD. DISPLACED W/ 174 BBLS CLAYTREAT WATER, 155 BBLS INTO DISPLACEMENT LOST RETURNS, 20 BBLS SPACER TO PIT, 2.5 BACK TO TRUCK. PLUG BACK TO 11,248'. BUMPED PLUG W/ 3800 PSI, 500 OVER FINAL LIFT OF 3300 PSI. RD CEMENTERS AND CLEANED PITS. RELEASED PIONEER RIG #54 ON DECEMBER 22, 2010 @ 06:00 HRS.

NAME (PLEASE PRINT) Andy Lytle	PHONE NUMBER 720 929-6100	TITLE Regulatory Analyst
SIGNATURE N/A		DATE 12/22/2010

 Accepted by the
 Utah Division of
 Oil, Gas and Mining
FOR RECORD ONLY

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-3282-A
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 921-16P
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0962 FSL 0491 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESE Section: 16 Township: 09.0S Range: 21.0E Meridian: S		9. API NUMBER: 43047392540000
PHONE NUMBER: 720 929-6515 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input checked="" type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 2/7/2011			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
 THE SUBJECT WELL WAS PLACED ON PRODUCTION ON FEBUARY 07, 2011 AT 7:00 P.M. THE CHRONOLOGICAL WELL HISTORY WILL BE SUBMITTED WITH THE WELL COMPLETION REPORT.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

NAME (PLEASE PRINT) Andy Lytle	PHONE NUMBER 720 929-6100	TITLE Regulatory Analyst
SIGNATURE N/A		DATE 2/9/2011

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8
(highlight changes)

5. LEASE DESIGNATION AND SERIAL NUMBER:
ML 3282A

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL ☐ GAS WELL ☒ DRY ☐ OTHER _____

b. TYPE OF WORK: NEW WELL ☒ HORIZ. LATS. ☐ DEEP-EN ☐ RE-ENTRY ☐ DIFF. RESVR. ☐ OTHER _____

2. NAME OF OPERATOR:
KERR MCGEE OIL & GAS ONSHORE, L.P.

3. ADDRESS OF OPERATOR: P.O.BOX 173779 CITY **DENVER** STATE **CO** ZIP **80217** PHONE NUMBER: **(720) 929-6100**

4. LOCATION OF WELL (FOOTAGES)
AT SURFACE: **SESE 962 FSL 491 FEL S16, T9S, R21E**

AT TOP PRODUCING INTERVAL REPORTED BELOW:

AT TOTAL DEPTH:

6. IF INDIAN, ALLOTTEE OR TRIBE NAME
UTE TRIBE

7. UNIT or CA AGREEMENT NAME
UTU63047A

8. WELL NAME and NUMBER:
NBU 921-16P

9. API NUMBER:
4304739254

10 FIELD AND POOL, OR WILDCAT
NATURAL BUTTES

11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:
SESE 16 9S 21E S

12. COUNTY **UINTAH** 13. STATE **UTAH**

14. DATE SPUDDED: **10/12/2010** 15. DATE T.D. REACHED: **12/19/2010** 16. DATE COMPLETED: **2/7/2011** ABANDONED ☐ READY TO PRODUCE ☒

17. ELEVATIONS (DF, RKB, RT, GL):
4810 GL

18. TOTAL DEPTH: MD **11,290** TVD **11,285** 19. PLUG BACK T.D.: MD **11,269** TVD **11,264** 20. IF MULTIPLE COMPLETIONS, HOW MANY? *

21. DEPTH BRIDGE MD PLUG SET: TVD

22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each)

☒ CBL-BHP-HDIL/ZDL/CNGR

23. WAS WELL CORED? NO ☒ YES ☐ (Submit analysis)
WAS DST RUN? NO ☒ YES ☐ (Submit report)
DIRECTIONAL SURVEY? NO ☒ YES ☒ (Submit copy)

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
20"	14" STL	36.7#		40		28			
11"	8 5/8" IJ-55	28#		2,816		645		0	
7 7/8"	4 1/2" P110	11.6#		11,285		2,045		150	

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2 3/8"	9,969							

26. PRODUCING INTERVALS **USAD**

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A) MESAVERDE	8,302	11,080			8,302 11,080	0.36	178	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(B)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(C)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

27. PERFORATION RECORD

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
8302 - 11,080	PUMP 12,558 BBLs SLICK H2O & 377,101 LBS 30/50 SAND

29. ENCLOSED ATTACHMENTS:

☐ ELECTRICAL/MECHANICAL LOGS ☐ GEOLOGIC REPORT ☐ DST REPORT ☐ DIRECTIONAL SURVEY
☐ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION ☐ CORE ANALYSIS ☐ OTHER: _____

30. WELL STATUS:

PROD

RECEIVED

MAR 29 2011

(CONTINUED ON BACK)

DIV. OF OIL, GAS & MINING

31. INITIAL PRODUCTION

INTERVAL A (As shown in Item #28)

DATE FIRST PRODUCED: 2/7/2011		TEST DATE: 2/11/2011		HOURS TESTED: 24		TEST PRODUCTION RATES: →	OIL – BBL: 0	GAS – MCF: 2,746	WATER – BBL: 271	PROD. METHOD: FLOWING
CHOKE SIZE: 18/64	TBG. PRESS. 2,300	CSG. PRESS. 3,000	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL: 0	GAS – MCF: 2,746	WATER – BBL: 271	INTERVAL STATUS: PROD

INTERVAL B (As shown in Item #28)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL C (As shown in Item #28)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL D (As shown in Item #28)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof. Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
GREEN RIVER	1,644				
BIRD'S NEST	1,995				
MAHOGANY	2,350				
WASATCH	5,041	7,997			
MESAVERDE	7,997	11,290	TD		

35. ADDITIONAL REMARKS (Include plugging procedure)

Attached is the chronological well history and final survey. Completion chrono details individual frac stages.

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) ANDREW LYTLETITLE REGULATORY ANALYSTSIGNATURE DATE 3/22/2011

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-16P			Spud Conductor: 10/12/2010				Spud Date: 10/17/2010		
Project: UTAH-UINTAH			Site: NBU 921-16P				Rig Name No: PROPETRO/, PIONEER 54/54		
Event: DRILLING			Start Date: 9/30/2010				End Date: 12/22/2010		
Active Datum: RKB @4,829.00ft (above Mean Sea Level)			UWI: SE/SE/0/9/S/21/E/16/0/0/26/PM/S/962.00/E/0/610.00/0/0						
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation	
10/16/2010	8:00 - 23:00	15.00	MIRU	01	A	P		MOVE RIG ONTO LOCATION, DRESS TOP OF CONDUCTOR. INSTALL DIVERTER HEAD AND BOWIE LINE. BUILD DITCH. MOVE RIG OVER HOLE AND RIG UP.. SET CATWALK AND PIPE RACKS. RIG UP AND PRIME PIT PUMP AND MUD PUMP.	
	23:00 - 0:00	1.00	MAINT	08	B	X		WORK ON PUMP, SUCTION MANIFOLD CRACKED.	
10/17/2010	0:00 - 8:00	8.00	MAINT	08	B	X		WORK ON MUD PUMP AND PIT PUMP	
	8:00 - 8:30	0.50	PRPSPD	01	B	P		P/U STRAIGHT HOUSING HUNTING MTR SN 8085. 7/8 LOBE .16 RPM. M/U Q506 SN 701794 1ST RUN, W/ 6-18'S. INSTALL RUBBER.	
	8:30 - 0:00	15.50	DRLSUR	02	A	P		SPUD SURFACE 10/17/2010 @ 08:30 HRS. DRILL 11" SURFACE HOLE F/40'- 1420' (1380' 89'/HR) PSI ON/ OFF 1150/1000, UP/ DOWN/ ROT 51/45/48. SURVEY @ 500' 1 DEG, SURVEY @ 1000' = .5 DEG	
10/18/2010	0:00 - 20:30	20.50	DRLSUR	02	A	P		DRILL 11" SURFACE HOLE F/1420'-2840' (1420' 69'/HR) PSI ON/ OFF 1320/1120, UP/ DOWN/ ROT 67/62/65. SURVEY @ 2800' .7 DEG 229 AZ; DRLG W/ H2O, FULL RETURNS CIRC AND COND HOLE CLEAN	
	20:30 - 22:00	1.50	DRLSUR	05	A	P		TOOH, LDDS AND BHA	
	22:00 - 0:00	2.00	DRLSUR	06	A	P		TOOH, LDDS AND BHA	
10/19/2010	0:00 - 2:30	2.50	DRLSUR	06	A	P		TOOH, LDDS AND BHA	
	2:30 - 5:30	3.00	DRLSUR	05	A	S		CIRCULATE OUT GAS WHILE WAITING FOR LOAD OF MUD TO KILL WELL.	
	5:30 - 6:30	1.00	DRLSUR	06	A	P		FINISH LAYING DOWN BHA	
	6:30 - 7:30	1.00	CSG	12	A	P		MOVE CATWALK AND PIPE RACKS, MOVE CSG OVER TO WORK AREA	
	7:30 - 11:30	4.00	CSG	12	C	P		HOLD SAFETY MEETING, RUN CSG. RAN 63JTS OF 8-5/8", 28#, IJ-55, 8 RND CSG W/ LTC THREADS. LANDED FLOAT SHOE @ 2797' KB. RAN BAFFLE PLATE IN TOP OF SHOE JT LANDED 2750.90' KB. FILL CSG @ 500', 1500', AND 2790'.	
	11:30 - 12:00	0.50	RDMO	01	E	P		RIG DOWN RIG, MOVE OUT, RELEASE RIG 10/19/2010 @ 12:00	

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-16P		Spud Conductor: 10/12/2010		Spud Date: 10/17/2010	
Project: UTAH-UINTAH		Site: NBU 921-16P		Rig Name No: PROPETRO/, PIONEER 54/54	
Event: DRILLING		Start Date: 9/30/2010		End Date: 12/22/2010	
Active Datum: RKB @4,829.00ft (above Mean Sea Level)		UWI: SE/SE/0/9/S/21/E/16/0/0/26/PM/S/962.00/E/0/610.00/0/0			

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	12:00 - 16:00	4.00	CSG	12	E	P		<p>HOLD SAFETY MEETING. INSTALL CEMENT HEAD. PSI TEST TO 2000 PSI. PUMP 20 BBLS OF 8.3# H2O AHEAD. FULL CIRC. PUMP 20 BBLS OF 8.4# GEL WATER AHEAD. FULL CIRC. PUMP 220 SX (149.6 BBLS) OF 11# 3.82 YIELD LEAD CMT, PUMP 200 SX (40.9 BBLS) OF 15.8# 1.15 YIELD TAIL(2% CALC, 1/4# /SK OF FLOCELE). FULL CIRC. DROP PLUG ON FLY AND DISPLACE W/174.9 BBLS OF 8.3# H2O. PARTIAL RETURNS. LIFT PRESSURE WAS 100 PSI, BUMP PLUG AND HOLD 700 PSI FOR 5 MIN. FLOAT HELD. EST TOC OF TAIL 1490'</p> <p>TOP OUT DOWN 1" PUMP 125 SX (25.6 BBLS), PUMP 100 SX (20.4 BBLS) DOWN BACK SIDE OF 15.8# 1.15 YIELD TAIL(4 % CALC, 1/4# /SK OF FLOCELE). RIG DOWN CEMENTERS AND RELEASE CEMENTERS 16:00 HRS.</p> <p>CONDUCTOR CASING: Cond. Depth set: 40' Cement sx used: 28</p> <p>SPUD DATE/TIME: 10/17/2010 18:30</p> <p>SURFACE HOLE: Surface From depth: 40' Surface To depth: 2,840 Total SURFACE hours: 36 Surface Casing size: 8.625" # of casing joints ran: 63 Casing set MD: 2,797' # sx of cement: 220 SKS LEAD, 425 SKS TAIL AND TOP OUT Cement blend (ppg): 11# LEAD, 15.8# ON TAIL CMTS Cement yield (ft3/sk): 3.82 LEAD, 1.15 YIELD ON TAIL CMTS # of bbls to surface:0BBL Describe cement issues: FULL CIRC DURING CMT JOB Describe hole issues: GASSY</p>
12/7/2010	18:00 - 0:00	6.00	DRLPRO	01	E	P		RDRT PREPARE TO MOVE TO NBU 921-16P
12/8/2010	0:00 - 7:00	7.00	DRLPRO	01	E	P		RDRT
	7:00 - 18:00	11.00	DRLPRO	01	A	P		MOVE RIG TO NBU 921-16P, 80% MOVED
	18:00 - 0:00	6.00	DRLPRO	21	C	P		WAIT ON DAYLIGHT
12/9/2010	0:00 - 7:00	7.00	DRLPRO	21	C	P		WAIT ON DAYLIGHT
	7:00 - 17:00	10.00	DRLPRO	01	A	P		FINISH RIG MOVE, TRUCKS & CRANE LEFT LOC @ 17:00
	17:00 - 0:00	7.00	DRLPRO	01	B	P		RURT
12/10/2010	0:00 - 4:00	4.00	DRLPRO	14	A	P		N/U BOPE
	4:00 - 9:00	5.00	DRLPRO	15	A	P		TEST BOPE, RAMS & ALL VALVES 250 LOW 5000 HIGH, ANN 250-2500, CASING 1500 F/ 30 MIN
	9:00 - 9:30	0.50	DRLPRO	14	B	P		INSTALL WEAR BUSHING
	9:30 - 0:00	14.50	DRLPRO	08	B	P		SCHEDULED MAINTENANCE, REPLACE SEALS IN TOPDRIVE, INSTALL NEW LINE ON SERVICE LOOP
12/11/2010	0:00 - 13:00	13.00	DRLPRO	08	B	P		SCHEDULED MAINTANANCE, REPAIR TOPDRIVE

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-16P			Spud Conductor: 10/12/2010				Spud Date: 10/17/2010	
Project: UTAH-UINTAH			Site: NBU 921-16P				Rig Name No: PROPETRO/, PIONEER 54/54	
Event: DRILLING			Start Date: 9/30/2010				End Date: 12/22/2010	
Active Datum: RKB @4,829.00ft (above Mean Sea Level)			UWI: SE/SE/0/9/S/21/E/16/0/0/26/PM/S/962.00/E/0/610.00/0/0					
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	13:00 - 18:00	5.00	DRLPRO	06	A	P		HPJSM W/ RIG & P/U CREWS, P/U BIT-MM-DIR TOOLS & SCRIBE, P/U BHA & 52 JTS D/P & R.D P/U CREW
	18:00 - 20:00	2.00	DRLPRO	08	A	P		CHANGE OUT SAVER SUB & TOR 2 COMPRESSION RINGS ON TOPDRIVE
	20:00 - 20:30	0.50	DRLPRO	14	B	P		INSTALL ROT RUBBER, PSI TEST MUD LINES, PRE-SPUD INSPECTION
	20:30 - 21:30	1.00	DRLPRO	08	B	P		REBUILD SWIVEL PACKING QUICK CHANGE
	21:30 - 23:30	2.00	DRLPRO	02	F	P		DRLG CEMENT, F/E & OPEN HOLE TO 2855'
	23:30 - 0:00	0.50	DRLPRO	02	D	P		DRLG F/ 2855 TO 2922', 67' @ 134' PH, WOB 16, SPM 120, GPM 454, RPM 50, MM 97, PSI ON/OFF 1400-1150, DIFF 250-400, TOR ON/OFF 2-0, 100% ROT, CIRC RESERVE PIT W/ GEL & POLY SWEEPS
12/12/2010	0:00 - 15:30	15.50	DRLPRO	02	B	P		DRLG F/ 2922 TO 4635', 1713' @ 110.5' PH, WOB 18, MW 8.4, VIS 26, CIRC RESERVE W/ GEL & POLY SWEEPS, SPM 120, GPM 454, RPM 50, MM 97, PSI ON/OFF 1550-1250, DIFF 250-400, TOR ON/OFF 6-4 K, BOP DRILL 75 SEC, F/T ANN & HCR SLIDE 62' IN 1.84 HRS=33.6' PH
	15:30 - 16:00	0.50	DRLPRO	07	A	P		ROT 1651' IN 13.66 HRS=120.8' PH
	16:00 - 0:00	8.00	DRLPRO	02	B	P		SERVICE RIG
								DRLG F/ 4635 TO 5645', 1010' @ 126.3' PH, WOB 18, MW 8.4, VIS 27, CIRC RESERVE W/ GEL & POLY SWEEPS, SPM 120, GPM 454, RPM 50, MM 97, PSI ON/OFF 1900-1700, DIFF 200-400, TOR ON/OFF 7-5 K, 100% ROT
12/13/2010	0:00 - 16:00	16.00	DRLPRO	02	B	P		DRLG F/ 5645 TO 7101', 1456' @ 91' PH, WOB 18, MW 8.4, VIS 27, CIRC RESERVE W/ GEL & POLY SWEEPS, SPM 120, GPM 454, RPM 50, MM 97, PSI ON/OFF 1900-1650, DIFF 200-400, TOR ON/OFF 7-4, SLIDES 62' IN 2.66 HRS=23.3' PH
	16:00 - 16:30	0.50	DRLPRO	07	A	P		ROT 1394' IN 13.34 HRS=104.5' PH
	16:30 - 0:00	7.50	DRLPRO	02	B	P		SERVICE RIG
								DRLG F/ 7101 TO 7460', 359' @ 47.9' PH, WOB 18-20, START MUD UP @ 7150, MW 9.2, VIS 35, SPM 120, GPM 454, RPM 50, MM 97, PSI ON/OFF 2100-1800, DIFF 200-400, TOR ON/OFF 7-4
								SLIDES 15' IN 1.83 HRS=8.2' PH
								ROT 344' IN 5.67 HRS= 60.7' PH
12/14/2010	0:00 - 15:30	15.50	DRLPRO	02	B	P		DRLG F/ 7460 TO 8335', 875' @ 56.5' PH, WOB 20, MW 10, VIS 36, SPM 120, GPM 454, RPM 50, MM 97, PSI ON/OFF 2300-2100, DIFF 150-250, TOR 7-4 K, SERVICE RIG
	15:30 - 16:00	0.50	DRLPRO	07	A	P		
	16:00 - 0:00	8.00	DRLPRO	02	B	P		DRLG F/ 8335 TO 8870', 455' @ 56.9' PH, WOB 22, MW 10.6, VIS 40, SPM 120, GPM 454, RPM 50, MM 97, PSI ON/OFF 2600-2300, DIFF 200-300, TOR 7-5 K,
12/15/2010	0:00 - 2:00	2.00	DRLPRO	02	B	P		DRLG F/ 8790 TO 8920', 130' @ 65' PH, MW 10.6, VIS 40, WOB 20, SPM 110, GPM 424, RPM 50, MM 86, PSI ON/OFF 2600-2400, DIFF 200-400, TOR ON/OFF 7-5 K
	2:00 - 2:30	0.50	DRLPRO	22	H	X		WORK TIGHT HOLE @ 8920'
	2:30 - 15:30	13.00	DRLPRO	02	B	P		DRLG F/ 8920 TO 9378', 458' @ 35.3' PH, WOB 18, MW 11.6, VIS 40, SPM 110, GPM 424, RPM 50, MM 86, PSI ON/OFF 2600-2400, DIFF 200-400, TOR 7-5 K
	15:30 - 16:00	0.50	DRLPRO	07	A	P		SERVICE RIG

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-16P		Spud Conductor: 10/12/2010	Spud Date: 10/17/2010
Project: UTAH-UINTAH		Site: NBU 921-16P	Rig Name No: PROPETRO/, PIONEER 54/54
Event: DRILLING		Start Date: 9/30/2010	End Date: 12/22/2010
Active Datum: RKB @4,829.00ft (above Mean Sea Level)		UWI: SE/SE/0/9/S/21/E/16/0/0/26/PM/S/962.00/E/0/610.00/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
12/16/2010	16:00 - 20:30	4.50	DRLPRO	02	B	P		DRLG F/ 9378 TO 9520', 142' @ 31.5' PH, WOB 20, SPM 110, GPM 424, RPM 50, MM 86, PSI ON/OFF 2800-2600, DIFF 150-350, TOR ON/OFF 7-5 K CIRC & COND HOLE F/ TRIP, MIX PILL
	20:30 - 21:30	1.00	DRLPRO	05	C	P		POOH W/ BIT #1
	21:30 - 23:00	1.50	DRLPRO	06	A	P		WORK TIGHT HOLE @ 5000', BACK REAM 60'
	23:00 - 0:00	1.00	DRLPRO	22	A	X		BACK REAM 60' @ 5000', MIX PILL TO POOH
	0:00 - 0:30	0.50	DRLPRO	22	A	X		POOH L/D MM & BIT #1, P/U BIT #2 & MM, TIH
	0:30 - 7:00	6.50	DRLPRO	06	A	P		WASH & REAM 40' TO BOTTOM 5' FILL
	7:00 - 7:30	0.50	DRLPRO	03	D	P		DRLG F/ 9520' TO 9956', 436' @ 58.1' PH, WOB 18, MW 12, VIS 43, LCM 5%, SPM 120, GPM 454, RPM 50, MM 76, PSI ON/OFF 2650-2500, DIFF 100-250, TOR ON/OFF 7-5 K
	7:30 - 15:00	7.50	DRLPRO	02	B	P		SERVICE RIG, F/T ANN & HCR
12/17/2010	15:00 - 15:30	0.50	DRLPRO	07	A	P		DRLG F/ 9956' TO 10320', 800' @ 50' PH, WOB 20, MW 12.8, VIS 48, LCM 5%, SPM 115, GPM 435, RPM 50, MM 70, PSI ON/OFF 2800-2600, DIFF 100-250, TOR 9-6 K
	15:30 - 0:00	8.50	DRLPRO	02	B	P		DRLG F/ 10320 TO 10372', 52' @ 11.5
	0:00 - 4:30	4.50	DRLPRO	02	B	P		LOST RETURNS, PULL 5 STDS, MIX LCM & BUILD VOLUME
	4:30 - 10:30	6.00	DRLPRO	22	G	X		DRLG F/ 10372 TO 10395', 23' PH, WOB 24, MW 12.7, VIS 48, LCM 20%, SPM 115, GPM 435, RPM 50, MM 87, PSI ON/OFF 2800-2600, DIFF 100-200, TOR 9-3 K
	10:30 - 12:00	1.50	DRLPRO	02	B	P		CIRC & COND MUD F/ TRIP
	12:00 - 13:00	1.00	DRLPRO	05	C	P		POOH W/ BIT #2, P/U BIT #3 TIH, 2 PLUGGED JETS, RUBBER & A ROCK, TRIP WAS CLEAN W/ 5' FILL
	13:00 - 22:00	9.00	DRLPRO	06	A	P		DRLG F/ 10395 TO 10435', 40' @ 20' PH, WOB 18, MW 12.7, VIS 48, LCM 20%, SPM 118, GPM 446, RPM 50, MM 97, PSI ON/OFF 2600-2400, DIFF 150-300, TOR 6-4 K
	22:00 - 0:00	2.00	DRLPRO	02	B	P		DRLG F/ 10435 TO 10718', 283' @ 21.8' PH, WOB 20, MW 12.8, VIS 47, LCM 20%, SPM 115, GPM 435, RPM 50, MM 91, PSI ON/OFF 2600-2400, DIFF 100-250, TOR 8-6 K
12/18/2010	0:00 - 13:00	13.00	DRLPRO	02	B	P		SERVICE RIG
	13:00 - 13:30	0.50	DRLPRO	07	A	P		DRLG F/ 10718 TO 10945', 227' @ 21.6' PH, WOB 24, MW 12.8, VIS 51, LCM 20%, SPM 115, GPM 435, RPM 50, MM 91, PSI ON/OFF 2700-2500, DIFF 100-250, TOR 9-6 K
	13:30 - 0:00	10.50	DRLPRO	02	B	P		DRLG F/ 10945 TO 11194', 249' @ 20.75' PH, WOB 24, MW 12.9, VIS 49, LCM 20%, SPM 115, GPM 435, RPM 40-50, MM 91, PSI ON/OFF 2800-2600, DIFF 100-250, TOR 10-6 K
	0:00 - 12:00	12.00	DRLPRO	02	B	P		SERVICE RIG
12/19/2010	12:00 - 12:30	0.50	DRLPRO	07	A	P		DRLG F/ 11194 TO 11290', TD WELL 12-19-10 @ 18:30, 96' @ WOB 24, MW 13.1, VIS 50, LCM 20%, SPM 115, GPM 435, RPM 40-50, MM 91, PSI ON/OFF 2900-2600, DIFF 100-250, TOR 10-6 K
	12:30 - 16:30	4.00	DRLPRO	02	B	P		CIRC & COND HOLE FOR WIPER TRIP
	16:30 - 18:00	1.50	DRLPRO	05	C	P		SHORT TRIP TO SHOE
	18:00 - 0:00	6.00	DRLPRO	06	E	P		SHORT TRIP TO SHOE
	0:00 - 1:00	1.00	DRLPRO	06	E	P		CIRC & COND FOR POOH TO LOG
	1:00 - 3:00	2.00	DRLPRO	05	C	P		POOH FOR OPEN HOLE LOGS, L/D DIR TOOLS
	3:00 - 9:00	6.00	DRLPRO	06	B	P		
12/20/2010								

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-16P			Spud Conductor: 10/12/2010				Spud Date: 10/17/2010	
Project: UTAH-UINTAH			Site: NBU 921-16P				Rig Name No: PROPETRO/, PIONEER 54/54	
Event: DRILLING			Start Date: 9/30/2010				End Date: 12/22/2010	
Active Datum: RKB @4,829.00ft (above Mean Sea Level)			UWI: SE/SE/0/9/S/21/E/16/0/0/26/PM/S/962.00/E/0/610.00/0/0					
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
12/21/2010	9:00 - 17:30	8.50	DRLPRO	11	C	P		HPJSM W/ RIG & LOGGING CREWS, R/U & RUN TRIPLE COMBO-OPEN HOLE LOGS TO 11,284', R/D
	17:30 - 19:00	1.50	DRLPRO	06	E	P		P/U ROLLER CONE & BIT SUB, TIH TO SHOE
	19:00 - 20:00	1.00	DRLPRO	09	A	P		CUT & SLIP 120' DRLG LINE
	20:00 - 0:00	4.00	DRLPRO	06	E	P		TIH, WASH 120' TO BOTTOM W/ 5' FILL, 10' FLARE F/ @ 10 MIN
	0:00 - 2:30	2.50	DRLPRO	05	C	P		CIRC & COND HOLE, HPJSM W/ RIG & L/D CREWS, MIX & PUMP PILL
	2:30 - 9:30	7.00	DRLPRO	06	A	P		LDDS
	9:30 - 10:00	0.50	DRLPRO	07	A	P		SERVICE RIG
	10:00 - 10:30	0.50	DRLPRO	14	B	P		PULL WEAR BUSHING
	10:30 - 20:30	10.00	DRLPRO	12	C	P		HPJSM W/ RIG & CASING CREWS, R/U & RUN 265 JTS + 2 MARKER WASATCH @ 5035, MESA @ 8050, CASING TO 11285', R/D
	20:30 - 22:00	1.50	DRLPRO	05	D	P		CIRC & COND HOLE, HPJSM W/ RIG & CEMENTING CREWS
12/22/2010	22:00 - 0:00	2.00	DRLPRO	12	E	P		TEST LINES TO 5000#, PUMP 40 BBLS SPACER, LEAD 655 SKS, 13.2 PPG 1.69 YLD, TAIL 1390 SKS 14.3 1.25 YLD, DROP PLUG & DISPLACE W/ 174 BBLS CLAYTREAT WATER, 155 BBLS INTO DISPLACEMENT LOST RETURNS, 20 BBLS SPACER TO PIT , 2.5 BACK TO TRUCK, PLUG BACK TO 11248', BUMP PLUG W/ 3800PSI 500 OVER FINAL LIFT OF 3300 PSI
	0:00 - 0:30	0.50	DRLPRO	12	B	P		R/D CEMENTERS
	0:30 - 6:00	5.50	DRLPRO	14	A	P		FLUSH STACK, PULL ROT RUBBER,SET SLIP W/ 140 K, N/D & MAKE ROUGH CUT, CLEAN PITS & RELEASE RIG @ 06:00 12/22/10

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-16P		Spud Conductor: 10/12/2010	Spud Date: 10/17/2010
Project: UTAH-UINTAH		Site: NBU 921-16P	Rig Name No: PROPETRO/, PIONEER 54/54
Event: DRILLING		Start Date: 9/30/2010	End Date: 12/22/2010
Active Datum: RKB @4,829.00ft (above Mean Sea Level)		UWI: SE/SE/0/9/S/21/E/16/0/0/26/PM/S/962.00/E/0/610.00/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
------	-------------------	------------------	-------	------	-------------	-----	-----------------	-----------

6:00 - 6:00 0.00 DRLPRO

CONDUCTOR CASING:

Cond. Depth set: 40
Cement sx used: 28

SPUD DATE/TIME: 10/17/2010 0:00

SURFACE HOLE:

Surface From depth: 40
Surface To depth: 2,840
Total SURFACE hours: 36.00
Surface Casing size: 8 5/8
of casing joints ran: 63
Casing set MD: 2,797.0
sx of cement: LEAD 220, TAIL 425
Cement blend (ppg): LEAD 11, TAIL 15.8
Cement yield (ft3/sk): LEAD 3.82, TAIL 1.15
of bbls to surface: 0
Describe cement issues: FULL RETURNS
Describe hole issues: GASSY

PRODUCTION:

Rig Move/Skid start date/time: 12/7/2010 18:00
Rig Move/Skid finish date/time: 12/9/2010 17:00
Total MOVE hours: 47.0
Prod Rig Spud date/time: 12/11/2010 21:30
Rig Release date/time: 12/22/2010 6:00
Total SPUD to RR hours: 248.5
Planned depth MD 11,286
Planned depth TVD 11,286
Actual MD: 11,290
Actual TVD: 11,285
Open Wells \$: \$1,051,605
AFE \$: \$1,239,600
Open wells \$/ft: \$93.03

PRODUCTION HOLE:

Prod. From depth: 2,855
Prod. To depth: 11,290
Total PROD hours: 154
Log Depth: 11284
Float Collar Top Depth: 11248
Production Casing size: 4.5", P-110
of casing joints ran: 265
Casing set MD: 11,285.0
Stage 1
sx of cement: LEAD 655, TAIL 1390
Cement density (ppg): LEAD 13.2, TAIL 14.3
Cement yield (ft3/sk): LEAD 1.69, TAIL 1.25
Stage 2
sx of cement:
Cement density (ppg):
Cement yield (ft3/sk):
Top Out Cmt
sx of cement:
Cement density (ppg):
Cement yield (ft3/sk):
Est. TOC (Lead & Tail) or 2 Stage :
Describe cement issues:
Describe hole issues:

DIRECTIONAL INFO:

KOP:
Max angle:
Departure:

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-16P		Spud Conductor: 10/12/2010		Spud Date: 10/17/2010				
Project: UTAH-UINTAH		Site: NBU 921-16P		Rig Name No: PROPETRO/, PIONEER 54/54				
Event: DRILLING		Start Date: 9/30/2010		End Date: 12/22/2010				
Active Datum: RKB @4,829.00ft (above Mean Sea Level)		UWI: SE/SE/0/9/S/21/E/16/0/0/26/PM/S/962.00/E/0/610.00/0/0						
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
Max dogleg MD:								

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-16P		Spud Conductor: 10/12/2010	Spud Date: 10/17/2010
Project: UTAH-UINTAH	Site: NBU 921-16P		Rig Name No: SWABBCO 1/1
Event: COMPLETION	Start Date: 1/24/2011	End Date: 2/7/2011	
Active Datum: RKB @4,829.00ft (above Mean Sea Level)		UWI: SE/SE/0/9/S/21/E/16/0/0/26/PM/S/962.00/E/0/610.00/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
2/1/2011	7:00 - 7:15	0.25	COMP	48		P		JSA= PICKING UP TUBING
	7:15 - 17:00	9.75	COMP	30		P		RU RIG ND WELLHEAD NU BOPS TALLEY & PU TUBING TO 8200' POOHTO 4000' SDFN.
2/2/2011	7:00 - 7:15	0.25	COMP	48		P		JSA= 27 BELOW KEEPING WARM
	7:15 - 15:00	7.75	COMP	30				0 PSI ON WELL POOH W/ REMAINING TUBING RD FLOOR & TUBING EQUIP ND BOPS NU FRAC VALVES RU FLOOR & TARPS W/ HEATER FILL HOLE W/ RIG PUMP NU TESTER & PRESS TEST AS PER PROC TO 9000# MI RU W/L PREP TO FRAC IN AM
2/3/2011	7:00 - 15:00	8.00	COMP	30		P		STANDBY
2/4/2011	6:00 - 6:15	0.25	COMP	48		P		JSA= FRAC & PERF SAFETY
	6:15 - 19:00	12.75	COMP	30		P		0 PSI ON WELL STAGE #1] PU RIH W/ PERF GUN, PERF MESA VERDE USING 3-3/8" EXPEND, 23 GRAM, 0.36" HOLES 11078'-11080', 4 SPF, 90* PH, 8 HOLES, BRK DWN PERFS @ 6923# , ISIP= 4526# 10958'-10960', 3 SPF, 120* PH, 6 HOLES. 10946'-10948', 3 SPF, 120* PH, 6 HOLES. 10936'-10938', 3 SPF, 120* PH, 6 HOLES. 10930'-10932', 3 SPF, 120* PH, 6 HOLES. (32 HOLES) WHP= 0 ,BREAK DOWN PERF@ 4080# , INJ RT= 51.4 ,INJ PSI 6150# ,ISIP=3670# , FG= .77 , MP= 9094# , MR= 51.5 , AP= 7000# , AR= 51 , FG=.80 , ISIP= 4056# , NPI= 386# , BLS SLICK WTR PUMPED= 4349 , W/ 99262 #30/50 TLC. W/ 32/32 CALC PERFS OPEN 100%. STAGE #2] PU RIH W/ HALLI 10K CBP & PERF GUN, SET CBP @ 10902', PERF MESA VERDE USING 3-3/8" EXP, 23 GRAM, 0.36" HOLE. 10870'-10872', 4 SPF, 90* PH, 8 HOLES, BRK DWN PERFS @ , ISIP= 10840'-10842', 4 SPF, 90* PH, 8 HOLES 10804'-10806', 4 SPF, 90* PH, 8 HOLES 10779'-10781', 4 SPF, 90* PH, 8 HOLES. (32 HOLES) WHP= 3723# ,BREAK DOWN PERF@5276# , INJ RT= 51.4 ,INJ PSI= 6727# ,ISIP= 4169# , FG= .82 , MP= 8511# , MR= 51.6 , AP= 7100# , AR= 50.7 , FG= .81 , ISIP=4128# , NPI= -41 , BLS SLICK WTR PUMPED= 3556 , W/ 106178 #30/50 TLC. W/ 32 /32 CALC PERFS OPEN 100%. STAGE #3] PU RIH W/ HALLI 8K CBP & PERF GUN, SET CBP @ 10271', PERF MESA VERDE USING 3-3/8" EXP, 23 GRAM, 0.36" HOLE. 10219'-10221', 3 SPF, 120* PH, 6 HOLES. 10206'-10208', 3 SPF, 120* PH, 6 HOLES. 10180'-10181', 4 SPF, 90* PH, 4 HOLES. 9986'-9988', 3 SPF, 120* PH, 6 HOLES. (22 HOLES) SWIFN

US ROCKIES REGION

Operation Summary Report

Well: NBU 921-16P				Spud Conductor: 10/12/2010				Spud Date: 10/17/2010				
Project: UTAH-UINTAH				Site: NBU 921-16P					Rig Name No: SWABBCO 1/1			
Event: COMPLETION				Start Date: 1/24/2011						End Date: 2/7/2011		
Active Datum: RKB @4,829.00ft (above Mean Sea Level)					UWI: SE/SE/0/9/S/21/E/16/0/0/26/PM/S/962.00/E/0/610.00/0/0							
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation				
2/5/2011	7:00 - 7:15	0.25	COMP	48		P		JSA=				

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-16P		Spud Conductor: 10/12/2010	Spud Date: 10/17/2010
Project: UTAH-UINTAH	Site: NBU 921-16P		Rig Name No: SWABBCO 1/1
Event: COMPLETION	Start Date: 1/24/2011	End Date: 2/7/2011	
Active Datum: RKB @4,829.00ft (above Mean Sea Level)		UWI: SE/SE/0/9/S/21/E/16/0/0/26/PM/S/962.00/E/0/610.00/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	7:15 - 17:00	9.75	COMP	30		P		<p>STAGE #3] PERFS SHOT PREV NIGHT WHP= 2300 ,BREAK DOWN PERF@ 3717# , INJ RT= 51.4 ,INJ PSI = 6727# ,ISIP= 2879# , FG=.72 , MP= 6542# , MR= 53.7 , AP= 6200# , AR= 43 , FG=.74 , ISIP= 3080# , NPI= 201# , BLS SLICK WTR PUMPED= 704 , W/ 22593 #30/50 MESH W/ 5000# RESIN COAT IN TAIL. 14/22 CALC PERFS OPEN 64%</p> <p>STAGE #4] PU RIH W/ HALLI 8K CBP & PERF GUN, SET CBP @ 9806' , PERF MESA VERDE USING 3-3/8" EXP, 23 GRAM, 0.36" HOLE. 9754'-9756' , 4 SPF, 90* PH, 8 HOLES 9696'-9697' , 4 SPF, 90* PH, 4 HOLES 9656'-9657' , 4 SPF, 90* PH, 4 HOLES. 9600'-9602' , 3 SPF, 120* PH, 6 HOLES. (22 HOLES)</p> <p>WHP= 1380# ,BREAK DOWN PERF@ 3622# , INJ RT= 38 ,INJ PSI 6245# ,ISIP= 2879# , FG= .72 , MP=6608# , MR= 51.6 , AP= 6150# , AR= 44 , FG=.78 , ISIP= 3360# , NPI= 83 , BLS SLICK WTR PUMPED= 686 , W/ 22737 #30/50 MESH. W/ 18 /22 CALC PERFS OPEN 82%</p> <p>STAGE #5] PU RIH W/ HALLI 8K CBP & PERF GUN, SET CBP @ 9507' , PERF MESA VERDE USING 3-3/8" EXP, 23 GRAM, 0.36" HOLE 9456'-9457' , 4 SPF, 90* PH, 4 HOLES. 9440'-9441' , 4 SPF, 90* PH, 4 HOLES. 9370'-9371' , 4 SPF, 90* PH, 4 HOLES. 9336'-9337' , 3 SPF, 120* PH, 3 HOLES. 9324'-9325' , 3 SPF, 120* PH, 3 HOLES. 9238'-9239' , 4 SPF, 90* PH, 4 HOLES. (22 HOLES)</p> <p>WHP= 1620# ,BREAK DOWN PERF@3943# , INJ RT= 37.9 ,INJ PSI = 6435# ,ISIP= 2468# , FG= .70 , MP= 6715# , MR= 50.9 , AP= 6000# , AR= 45.5 , FG=.73 , ISIP= 2820# , NPI= 352# , BLS SLICK WTR PUMPED= 993 , W/ 37403 #30/50 MESH. W/5000# RESIN IN TAIL 14/22 CALC PERFS OPEN 64%</p> <p>STAGE #6] PU RIH W/ HALLI 8K CBP & PERF GUN, SET CBP @ 8742' , PERF MESA VERDE USING 3-3/8" EXP, 23 GRAM, 0.36" HOLE. 8690'-8692' , 4 SPF, 90* PH, 8 HOLES. 8600'-8602' , 4 SPF, 90* PH, 8 HOLES. 8562'-8564' , 4 SPF, 90* PH, 8 HOLES. (24 HOLES)</p> <p>WHP= 904# ,BREAK DOWN PERF@ 2659# , INJ RT= 53.4 ,INJ PSI= 5985# ,ISIP=2307# , FG= .70 , MP=6608 , MR= 51.4 , AP= 5350# , AR=49 , FG=.76 , ISIP= 2837# , NPI= 530# , BLS SLICK WTR PUMPED= 671 , W/ 23295 #30/50 MESH. W/ 5000# RESIN 18/24 CALC PERFS OPEN 75%</p> <p>STAGE #7] PU RIH W/ HALLI 8K CBP & PERF GUN, SET CBP @ 8446' , PERF MESA VERDE USING 3-3/8" EXP, 23 GRAM, 0.36" HOLE 8394'-8396' , 3 SPF, 120* PH, 6 HOLES. 8376'-8378' , 3 SPF, 120* PH, 6 HOLES. 8348'-8350' , 3 SPF, 120* PH, 6 HOLES. 8302'-8304' , 3 SPF, 120* PH, 6 HOLES. (24 HOLES)</p> <p>WHP=1020# ,BREAK DOWN PERF@ 3146# , INJ</p>

US ROCKIES REGION

Operation Summary Report

Well: NBU 921-16P			Spud Conductor: 10/12/2010			Spud Date: 10/17/2010		
Project: UTAH-UINTAH			Site: NBU 921-16P			Rig Name No: SWABBCO 1/1		
Event: COMPLETION			Start Date: 1/24/2011			End Date: 2/7/2011		
Active Datum: RKB @4,829.00ft (above Mean Sea Level)			UWI: SE/SE/0/9/S/21/E/16/0/0/26/PM/S/962.00/E/0/610.00/0/0					
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
								RT= 50.8 ,INJ PSI= 5139# ,ISIP=2083# , FG= .68 , MP= 6441# , MR= 51.7 , AP= 3850# , AR= 51.5 , FG= .72 , ISIP= 2403 , NPI= 321# , BLS SLICK WTR PUMPED= 1599 , W/ 64634 #30/50 MESH. W/ 5000# RESIN IN TAIL 24/24 CALC PERFS OPEN 100% PU SETTING TOOL & HALLI 8K CBP RIH SET @ 8230' FOR KILL PLUG RD FRAC EQUIP & W/L EQUIP SWIFW TOTAL FLUID PUMPED=12,558 BBLS TOTAL SAND = 377101 SCALE INHIB= 1266 GAL BIOCIDE= 230 JSA= WELL CONTROL
2/7/2011	7:00 - 7:15	0.25	COMP	48		P		

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-16P		Spud Conductor: 10/12/2010	Spud Date: 10/17/2010
Project: UTAH-UINTAH	Site: NBU 921-16P		Rig Name No: SWABBCO 1/1
Event: COMPLETION	Start Date: 1/24/2011	End Date: 2/7/2011	
Active Datum: RKB @4,829.00ft (above Mean Sea Level)		UWI: SE/SE/0/9/S/21/E/16/0/0/26/PM/S/962.00/E/0/610.00/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	7:15 - 19:00	11.75	COMP	30		P		<p>0 PSI ON WELL ND FRAC VALVES NU BOPS RU FLOOR & TUBING EQUIP PU 3-7/8" BIT POBC & 1.87XN NPL TIH TAG KILL PLUG @ 8230'</p> <p>PLUG #1] DRILL THRU HALLI 8K CBP @ 8230' IN 10 MIN W/ 100 # INCREASE</p> <p>PLUG #2] CONTINUE TO RIH TAG SAND @ 8400' (46' FILL) C/O & DRILL THRU HALLI 8K CBP @ 8446' IN 12 MIN W/0 INCREASE.</p> <p>PLUG #3] CONTINUE TO RIH TAG SAND @ 8692' (50' FILL) C/O & DRILL THRU HALLI 8K CBP @ 8742' IN 9 MIN W/200# INCREASE</p> <p>PLUG #4] CONTINUE TO RIH TAG SAND @ 9457' (50 FILL) C/O & DRILL THRU HALLI 8K CBP @ 9507' IN 12 MIN W/150# INCREASE. (450# ON WELL)</p> <p>PLUG #5] CONTINUE TO RIH TAG SAND @ 9761' (45' FILL) C/O & DRILL THRU HALLI 8K CBP @ 9806' IN 14 MIN W/200# INCREASE</p> <p>PLUG #6] CONTINUE TO RIH TAG SAND @ 10852' (50 FILL) C/O & DRILL THRU HALLI 8K CBP @ 10271' IN MIN W/150# INCREASE.</p> <p>PLUG #7] CONTINUE TO RIH TAG SAND @ (FILL) C/O & DRILL THRU HALLI 8K CBP @ 10902' IN MIN W/ INCREASE</p> <p>CONTINUE TO RIH TAG SAND @ C/O TO PBTD @ 11240' CIRC CLEAN POOH LD 40 JNTS LAND TUBING ON HANGER W/ 315 JNTS EOT @ 9969.43' RD FLOOR & TUBING EQUIP ND BOPS NU WELLHEAD DROP BALL PUMP OFF BIT @3300 PSI SWI 30 MIN TO ALLOW BALL TO FALL TURN WELL OVER TO FBC @ 18:30</p> <p>TUBING BROUGHT= 364 JNTS USED IN WELL= 315 ON FLOAT = 49</p> <p>TUBING DETAIL KB= 19.00 HANGER= 1.00 315 JNTS 2-3/8" L-80= 9947.23 POBS= 2.20 EOT= 9969.43</p>
2/11/2011	7:00 -			50				<p>WELL IP'D ON 2/11/11 - 2746 MCFD, 0 BOPD, 271 BWPD, CP 3000#, FTP 2300#, CK 18/64", LP 123#, 24 HRS</p>

WELL DETAILS: NBU 921-16P



GL 4810 & KB 19' @ 4829.00ft (PIONEER 54)

+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
0.00	0.00	14540409.32	2046663.15	40° 1' 49.300 N	109° 32' 55.702 W



Azimuths to True North
Magnetic North: 11.18°

Magnetic Field
Strength: 52400.5snT
Dip Angle: 65.90°
Date: 11/05/2010
Model: IGRF2010



PROJECT DETAILS: Uintah County, UT UTM12

Geodetic System: Universal Transverse Mercator (US Survey Feet)
Datum: NAD 1927 - Western US
Ellipsoid: Clarke 1866
Zone: Zone 12N (114 W to 108 W)
Location: SEC 16 T9S R21E
System Datum: Mean Sea Level



Scientific Drilling
Rocky Mountain Operations

Kerr McGee Oil and Gas Onshore LP

**Uintah County, UT UTM12
NBU 921-16P
NBU 921-16P**

OH

Design: OH

Standard Survey Report

21 December, 2010



Company: Kerr McGee Oil and Gas Onshore LP
Project: Uintah County, UT UTM12
Site: NBU 921-16P
Well: NBU 921-16P
Wellbore: OH
Design: OH

Local Co-ordinate Reference: Site NBU 921-16P
TVD Reference: GL 4810 & KB 19' @ 4829.00ft (PIONEER 54)
MD Reference: GL 4810 & KB 19' @ 4829.00ft (PIONEER 54)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM5000-RobertS-Local

Project Uintah County, UT UTM12
Map System: Universal Transverse Mercator (US Survey Feet) **System Datum:** Mean Sea Level
Geo Datum: NAD 1927 - Western US
Map Zone: Zone 12N (114 W to 108 W)

Site NBU 921-16P, SEC 16 T9S R21E
Site Position: **Northing:** 14,540,409.31 usft **Latitude:** 40° 1' 49.300 N
From: Lat/Long **Easting:** 2,046,663.14 usft **Longitude:** 109° 32' 55.702 W.
Position Uncertainty: 0.00 ft **Slot Radius:** 13.200 in **Grid Convergence:** 0.93 °

Well NBU 921-16P, 962' FSL, 491' FEL
Well Position **+N/-S** 0.00 ft **Northing:** 14,540,409.31 usft **Latitude:** 40° 1' 49.300 N
+E/-W 0.00 ft **Easting:** 2,046,663.14 usft **Longitude:** 109° 32' 55.702 W
Position Uncertainty 0.00 ft **Wellhead Elevation:** ft **Ground Level:** 4,810.00 ft

Wellbore OH
Magnetics **Model Name** **Sample Date** **Declination** **Dip Angle** **Field Strength**
(°) (°) (nT)
IGRF2010 11/05/2010 11.18 65.90 52,400

Design OH
Audit Notes:
Version: 1.0 **Phase:** ACTUAL **Tie On Depth:** 0.00
Vertical Section: **Depth From (TVD)** **+N/-S** **+E/-W** **Direction**
(ft) (ft) (ft) (°)
0.00 0.00 0.00 211.70

Survey Program **Date** 12/21/2010
From **To**
(ft) (ft)
Survey (Wellbore) **Tool Name** **Description**
15.00 2,815.00 Survey #1-SINGLE SHOT (OH) CB-MAG-SS Camera based mag single shot
2,870.00 11,290.00 Survey #2 SDI MWD PRODUCTION (OH) MWD SDI MWD - Standard ver 1.0.1

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
15.00	0.00	0.00	15.00	0.00	0.00	0.00	0.00	0.00	0.00
515.00	1.00	127.30	514.97	-2.64	3.47	0.43	0.20	0.20	0.00
1,015.00	0.50	200.60	1,014.94	-7.33	6.17	2.99	0.20	-0.10	14.66
2,015.00	1.20	283.00	2,014.85	-9.06	-5.56	10.63	0.12	0.07	8.24
2,815.00	1.90	175.10	2,814.67	-20.39	-12.60	23.97	0.32	0.09	-13.49
2,870.00	1.22	189.65	2,869.65	-21.88	-12.62	25.24	1.42	-1.24	26.45
FIRST SDI MWD PRODUCTION SURVEY									
2,965.00	1.10	198.62	2,964.63	-23.74	-13.08	27.07	0.23	-0.13	9.44
3,060.00	1.10	179.62	3,059.62	-25.51	-13.36	28.73	0.38	0.00	-20.00

Company: Kerr McGee Oil and Gas Onshore LP
Project: Uintah County, UT UTM12
Site: NBU 921-16P
Well: NBU 921-16P
Wellbore: OH
Design: OH

Local Co-ordinate Reference: Site NBU 921-16P
TVD Reference: GL 4810 & KB 19' @ 4829.00ft (PIONEER 54)
MD Reference: GL 4810 & KB 19' @ 4829.00ft (PIONEER 54)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM5000-RobertS-Local

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
3,155.00	1.04	181.02	3,154.60	-27.29	-13.37	30.24	0.07	-0.06	1.47
3,250.00	1.38	193.64	3,249.58	-29.26	-13.66	32.07	0.45	0.36	13.28
3,344.00	1.60	190.46	3,343.55	-31.65	-14.16	34.37	0.25	0.23	-3.38
3,439.00	1.58	181.10	3,438.51	-34.26	-14.43	36.73	0.27	-0.02	-9.85
3,534.00	1.45	187.80	3,533.48	-36.77	-14.61	38.96	0.23	-0.14	7.05
3,629.00	1.68	191.44	3,628.44	-39.32	-15.05	41.36	0.26	0.24	3.83
3,724.00	1.09	289.45	3,723.42	-40.39	-16.18	42.86	2.24	-0.62	103.17
3,819.00	3.05	317.20	3,818.36	-38.23	-18.75	42.38	2.26	2.06	29.21
3,913.00	2.80	306.15	3,912.24	-35.04	-22.31	41.53	0.65	-0.27	-11.76
4,008.00	2.37	299.32	4,007.14	-32.71	-25.89	41.44	0.56	-0.45	-7.19
4,103.00	2.20	290.69	4,102.06	-31.10	-29.31	41.87	0.40	-0.18	-9.08
4,198.00	2.03	271.56	4,197.00	-30.41	-32.70	43.06	0.76	-0.18	-20.14
4,293.00	1.36	315.08	4,291.96	-29.57	-35.18	43.64	1.48	-0.71	45.81
4,388.00	1.05	296.32	4,386.94	-28.39	-36.75	43.46	0.52	-0.33	-19.75
4,482.00	0.84	260.18	4,480.93	-28.12	-38.20	44.00	0.66	-0.22	-38.45
4,577.00	1.01	228.23	4,575.92	-28.80	-39.51	45.27	0.56	0.18	-33.63
4,672.00	1.28	216.79	4,670.90	-30.20	-40.77	47.13	0.37	0.28	-12.04
4,767.00	1.38	213.80	4,765.87	-32.01	-42.05	49.33	0.13	0.11	-3.15
4,862.00	1.50	203.14	4,860.84	-34.10	-43.17	51.70	0.31	0.13	-11.22
4,957.00	1.68	198.58	4,955.81	-36.56	-44.10	54.28	0.23	0.19	-4.80
5,052.00	1.64	198.41	5,050.77	-39.17	-44.98	56.96	0.04	-0.04	-0.18
5,147.00	1.53	191.16	5,145.73	-41.71	-45.65	59.47	0.24	-0.12	-7.63
5,241.00	1.48	187.43	5,239.70	-44.14	-46.05	61.76	0.12	-0.05	-3.97
5,336.00	1.79	184.27	5,334.66	-46.84	-46.32	64.19	0.34	0.33	-3.33
5,431.00	1.73	179.85	5,429.61	-49.75	-46.43	66.73	0.16	-0.06	-4.65
5,526.00	1.84	180.62	5,524.57	-52.71	-46.44	69.25	0.12	0.12	0.81
5,621.00	2.04	175.07	5,619.51	-55.92	-46.31	71.91	0.29	0.21	-5.84
5,716.00	2.03	174.07	5,714.45	-59.28	-45.99	74.60	0.04	-0.01	-1.05
5,811.00	2.28	170.21	5,809.39	-62.81	-45.50	77.35	0.30	0.26	-4.06
5,906.00	2.35	167.25	5,904.31	-66.58	-44.74	80.16	0.15	0.07	-3.12
6,001.00	2.49	166.77	5,999.23	-70.48	-43.84	83.01	0.15	0.15	-0.51
6,096.00	2.49	165.52	6,094.14	-74.49	-42.85	85.90	0.06	0.00	-1.32
6,190.00	2.56	160.35	6,188.04	-78.45	-41.64	88.62	0.25	0.07	-5.50
6,285.00	2.88	161.42	6,282.94	-82.71	-40.16	91.47	0.34	0.34	1.13
6,380.00	0.14	19.22	6,377.90	-84.86	-39.37	92.88	3.15	-2.88	-149.68
6,475.00	2.28	355.42	6,472.87	-82.87	-39.48	91.25	2.27	2.25	-25.05
6,570.00	2.09	358.30	6,567.80	-79.25	-39.68	88.28	0.23	-0.20	3.03
6,664.00	1.68	357.59	6,661.75	-76.16	-39.79	85.71	0.44	-0.44	-0.76
6,759.00	1.21	357.74	6,756.72	-73.77	-39.89	83.72	0.49	-0.49	0.16
6,853.00	0.94	347.09	6,850.70	-72.02	-40.10	82.35	0.36	-0.29	-11.33
6,948.00	1.92	333.91	6,945.67	-69.83	-40.97	80.95	1.08	1.03	-13.87
7,043.00	1.45	327.60	7,040.63	-67.39	-42.32	79.57	0.53	-0.49	-6.64
7,137.00	1.22	331.06	7,134.61	-65.51	-43.44	78.56	0.26	-0.24	3.68

Company: Kerr McGee Oil and Gas Onshore LP
Project: Uintah County, UT UTM12
Site: NBU 921-16P
Well: NBU 921-16P
Wellbore: OH
Design: OH

Local Co-ordinate Reference: Site NBU 921-16P
TVD Reference: GL 4810 & KB 19' @ 4829.00ft (PIONEER 54)
MD Reference: GL 4810 & KB 19' @ 4829.00ft (PIONEER 54)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM5000-RobertS-Local

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
7,232.00	2.60	349.97	7,229.55	-62.50	-44.30	76.46	1.58	1.45	19.91
7,327.00	2.32	349.89	7,324.47	-58.49	-45.02	73.42	0.29	-0.29	-0.08
7,421.00	1.97	353.78	7,418.40	-55.01	-45.52	70.72	0.40	-0.37	4.14
7,516.00	1.51	356.68	7,513.36	-52.14	-45.77	68.41	0.49	-0.48	3.05
7,611.00	1.22	351.85	7,608.33	-49.89	-45.99	66.61	0.33	-0.31	-5.08
7,707.00	1.26	5.66	7,704.31	-47.82	-46.03	64.88	0.31	0.04	14.39
7,801.00	1.07	17.46	7,798.29	-45.96	-45.67	63.10	0.32	-0.20	12.55
7,896.00	0.81	31.46	7,893.27	-44.54	-45.05	61.57	0.36	-0.27	14.74
7,991.00	1.17	40.06	7,988.26	-43.22	-44.07	59.94	0.41	0.38	9.05
8,087.00	0.99	41.09	8,084.24	-41.85	-42.90	58.15	0.19	-0.19	1.07
8,182.00	0.79	48.99	8,179.23	-40.80	-41.86	56.71	0.25	-0.21	8.32
8,277.00	0.72	67.99	8,274.22	-40.15	-40.82	55.61	0.27	-0.07	20.00
8,372.00	0.88	69.98	8,369.21	-39.67	-39.58	54.55	0.17	0.17	2.09
8,467.00	0.87	99.76	8,464.20	-39.55	-38.18	53.71	0.47	-0.01	31.35
8,562.00	0.97	119.19	8,559.19	-40.06	-36.77	53.41	0.34	0.11	20.45
8,656.00	1.23	124.20	8,653.17	-41.02	-35.24	53.41	0.29	0.28	5.33
8,751.00	1.31	143.81	8,748.15	-42.46	-33.76	53.87	0.46	0.08	20.64
8,845.00	1.55	150.85	8,842.12	-44.44	-32.50	54.89	0.32	0.26	7.49
8,941.00	1.94	157.67	8,938.08	-47.08	-31.25	56.48	0.46	0.41	7.10
9,036.00	2.06	158.87	9,033.02	-50.16	-30.03	58.45	0.13	0.13	1.26
9,131.00	2.27	159.50	9,127.95	-53.51	-28.75	60.64	0.22	0.22	0.66
9,228.00	2.47	164.92	9,224.87	-57.33	-27.53	63.25	0.31	0.21	5.59
9,323.00	2.36	159.81	9,319.78	-61.14	-26.33	65.86	0.25	-0.12	-5.38
9,416.00	2.04	161.02	9,412.72	-64.51	-25.13	68.09	0.35	-0.34	1.30
9,511.00	1.89	152.23	9,507.66	-67.49	-23.85	69.95	0.35	-0.16	-9.25
9,606.00	2.54	155.02	9,602.59	-70.79	-22.23	71.91	0.69	0.68	2.94
9,702.00	2.45	153.85	9,698.50	-74.56	-20.43	74.17	0.11	-0.09	-1.22
9,797.00	1.77	152.43	9,793.43	-77.68	-18.85	76.00	0.72	-0.72	-1.49
9,892.00	1.72	156.32	9,888.39	-80.29	-17.60	77.55	0.14	-0.05	4.09
9,987.00	1.52	146.33	9,983.35	-82.64	-16.33	78.89	0.36	-0.21	-10.52
10,082.00	1.48	135.23	10,078.32	-84.56	-14.77	79.70	0.31	-0.04	-11.68
10,177.00	2.18	142.04	10,173.27	-86.86	-12.79	80.62	0.77	0.74	7.17
10,273.00	2.39	152.63	10,269.19	-90.07	-10.75	82.28	0.49	0.22	11.03
10,368.00	2.66	156.31	10,364.10	-93.85	-8.95	84.55	0.33	0.28	3.87
10,463.00	2.69	155.42	10,459.00	-97.90	-7.14	87.04	0.05	0.03	-0.94
10,559.00	2.50	154.28	10,554.90	-101.83	-5.29	89.42	0.21	-0.20	-1.19
10,654.00	2.10	158.56	10,649.82	-105.32	-3.76	91.58	0.46	-0.42	4.51
10,749.00	2.54	155.62	10,744.74	-108.86	-2.25	93.80	0.48	0.46	-3.09
10,844.00	2.41	152.97	10,839.66	-112.55	-0.48	96.01	0.18	-0.14	-2.79
10,940.00	2.32	155.41	10,935.57	-116.12	1.25	98.13	0.14	-0.09	2.54
11,035.00	2.40	147.50	11,030.49	-119.54	3.12	100.07	0.35	0.08	-8.33
11,130.00	2.71	153.33	11,125.40	-123.23	5.20	102.11	0.43	0.33	6.14
11,225.00	2.87	150.86	11,220.29	-127.31	7.36	104.44	0.21	0.17	-2.60

LAST SDI MWD PRODUCTION SURVEY

Company: Kerr McGee Oil and Gas Onshore LP
Project: Uintah County, UT UTM12
Site: NBU 921-16P
Well: NBU 921-16P
Wellbore: OH
Design: OH

Local Co-ordinate Reference: Site NBU 921-16P
TVD Reference: GL 4810 & KB 19' @ 4829.00ft (PIONEER 54)
MD Reference: GL 4810 & KB 19' @ 4829.00ft (PIONEER 54)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM5000-RobertS-Local

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
11,290.00	2.87	150.86	11,285.21	-130.15	8.95	106.03	0.00	0.00	0.00
SDI PROJECTION TO TD									

Design Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates		Comment
		+N/-S (ft)	+E/-W (ft)	
2,870.00	2,869.65	-21.88	-12.62	FIRST SDI MWD PRODUCTION SURVEY
11,225.00	11,220.29	-127.31	7.36	LAST SDI MWD PRODUCTION SURVEY
11,290.00	11,285.21	-130.15	8.95	SDI PROJECTION TO TD

Checked By: _____ Approved By: _____ Date: _____



Scientific Drilling
Rocky Mountain Operations

Kerr McGee Oil and Gas Onshore LP

Uintah County, UT UTM12
NBU 921-16P
NBU 921-16P

OH

Design: OH

Survey Report - Geographic

21 December, 2010



Company:	Kerr McGee Oil and Gas Onshore LP	Local Co-ordinate Reference:	Site NBU 921-16P
Project:	Uintah County, UT UTM12	TVD Reference:	GL 4810 & KB 19' @ 4829.00ft (PIONEER 54)
Site:	NBU 921-16P	MD Reference:	GL 4810 & KB 19' @ 4829.00ft (PIONEER 54)
Well:	NBU 921-16P	North Reference:	True
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	EDM5000-RobertS-Local

Project	Uintah County, UT UTM12		
Map System:	Universal Transverse Mercator (US Survey Feet)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 - Western US		
Map Zone:	Zone 12N (114 W to 108 W)		

Site	NBU 921-16P, SEC 16 T9S R21E				
Site Position:		Northing:	14,540,409.31 usft	Latitude:	40° 1' 49.300 N
From:	Lat/Long	Easting:	2,046,663.14 usft	Longitude:	109° 32' 55.702 W
Position Uncertainty:	0.00 ft	Slot Radius:	13.200 in	Grid Convergence:	0.93 °

Well	NBU 921-16P, 962' FSL, 491' FEL					
Well Position	+N/-S	0.00 ft	Northing:	14,540,409.31 usft	Latitude:	40° 1' 49.300 N
	+E/-W	0.00 ft	Easting:	2,046,663.14 usft	Longitude:	109° 32' 55.702 W
Position Uncertainty		0.00 ft	Wellhead Elevation:	ft	Ground Level:	4,810.00 ft

Wellbore	OH				
Magnetics	Model Name	Sample Date	Declination	Dip Angle	Field Strength
	IGRF2010	11/05/2010	(°)	(°)	(nT)
			11.18	65.90	52,400

Design	OH				
Audit Notes:					
Version:	1.0	Phase:	ACTUAL	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD)	+N/-S	+E/-W	Direction	
	(ft)	(ft)	(ft)	(°)	
	0.00	0.00	0.00	211.70	

Survey Program	Date	12/21/2010			
From	To	Survey (Wellbore)	Tool Name	Description	
(ft)	(ft)				
15.00	2,815.00	Survey #1-SINGLE SHOT (OH)	CB-MAG-SS	Camera based mag single shot	
2,870.00	11,290.00	Survey #2 SDI MWD PRODUCTION (OH)	MWD SDI	MWD - Standard ver 1.0.1	

Survey									
Measured			Vertical			Map	Map		
Depth	Inclination	Azimuth	Depth	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
(ft)	(°)	(°)	(ft)	(ft)	(ft)	(usft)	(usft)		
0.00	0.00	0.00	0.00	0.00	0.00	14,540,409.31	2,046,663.14	40° 1' 49.300 N	109° 32' 55.702 W
15.00	0.00	0.00	15.00	0.00	0.00	14,540,409.31	2,046,663.14	40° 1' 49.300 N	109° 32' 55.702 W
515.00	1.00	127.30	514.97	-2.64	3.47	14,540,406.73	2,046,666.65	40° 1' 49.273 N	109° 32' 55.657 W
1,015.00	0.50	200.60	1,014.94	-7.33	6.17	14,540,402.08	2,046,669.43	40° 1' 49.227 N	109° 32' 55.622 W
2,015.00	1.20	283.00	2,014.85	-9.06	-5.56	14,540,400.16	2,046,657.72	40° 1' 49.210 N	109° 32' 55.773 W
2,815.00	1.90	175.10	2,814.67	-20.39	-12.60	14,540,388.72	2,046,650.88	40° 1' 49.098 N	109° 32' 55.864 W
2,870.00	1.22	189.65	2,869.65	-21.88	-12.62	14,540,387.23	2,046,650.88	40° 1' 49.083 N	109° 32' 55.864 W
FIRST SDI MWD PRODUCTION SURVEY									
2,965.00	1.10	198.62	2,964.63	-23.74	-13.08	14,540,385.37	2,046,650.45	40° 1' 49.065 N	109° 32' 55.870 W
3,060.00	1.10	179.62	3,059.62	-25.51	-13.36	14,540,383.59	2,046,650.20	40° 1' 49.047 N	109° 32' 55.873 W
3,155.00	1.04	181.02	3,154.60	-27.29	-13.37	14,540,381.81	2,046,650.22	40° 1' 49.030 N	109° 32' 55.874 W

Company: Kerr McGee Oil and Gas Onshore LP
Project: Uintah County, UT UTM12
Site: NBU 921-16P
Well: NBU 921-16P
Wellbore: OH
Design: OH

Local Co-ordinate Reference: Site NBU 921-16P
TVD Reference: GL 4810 & KB 19' @ 4829.00ft (PIONEER 54)
MD Reference: GL 4810 & KB 19' @ 4829.00ft (PIONEER 54)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM5000-RobertS-Local

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
3,250.00	1.38	193.64	3,249.58	-29.26	-13.66	14,540,379.83	2,046,649.96	40° 1' 49.010 N	109° 32' 55.877 W
3,344.00	1.60	190.46	3,343.55	-31.65	-14.16	14,540,377.43	2,046,649.50	40° 1' 48.987 N	109° 32' 55.884 W
3,439.00	1.58	181.10	3,438.51	-34.26	-14.43	14,540,374.82	2,046,649.27	40° 1' 48.961 N	109° 32' 55.887 W
3,534.00	1.45	187.80	3,533.48	-36.77	-14.61	14,540,372.31	2,046,649.13	40° 1' 48.936 N	109° 32' 55.890 W
3,629.00	1.68	191.44	3,628.44	-39.32	-15.05	14,540,369.75	2,046,648.73	40° 1' 48.911 N	109° 32' 55.895 W
3,724.00	1.09	289.45	3,723.42	-40.39	-16.18	14,540,368.67	2,046,647.62	40° 1' 48.900 N	109° 32' 55.910 W
3,819.00	3.05	317.20	3,818.36	-38.23	-18.75	14,540,370.78	2,046,645.01	40° 1' 48.922 N	109° 32' 55.943 W
3,913.00	2.80	306.15	3,912.24	-35.04	-22.31	14,540,373.91	2,046,641.41	40° 1' 48.953 N	109° 32' 55.988 W
4,008.00	2.37	299.32	4,007.14	-32.71	-25.89	14,540,376.19	2,046,637.79	40° 1' 48.976 N	109° 32' 56.035 W
4,103.00	2.20	290.69	4,102.06	-31.10	-29.31	14,540,377.74	2,046,634.34	40° 1' 48.992 N	109° 32' 56.078 W
4,198.00	2.03	271.56	4,197.00	-30.41	-32.70	14,540,378.37	2,046,630.94	40° 1' 48.999 N	109° 32' 56.122 W
4,293.00	1.36	315.08	4,291.96	-29.57	-35.18	14,540,379.17	2,046,628.45	40° 1' 49.007 N	109° 32' 56.154 W
4,388.00	1.05	296.32	4,386.94	-28.39	-36.75	14,540,380.33	2,046,626.86	40° 1' 49.019 N	109° 32' 56.174 W
4,482.00	0.84	260.18	4,480.93	-28.12	-38.20	14,540,380.57	2,046,625.40	40° 1' 49.022 N	109° 32' 56.193 W
4,577.00	1.01	228.23	4,575.92	-28.80	-39.51	14,540,379.88	2,046,624.10	40° 1' 49.015 N	109° 32' 56.210 W
4,672.00	1.28	216.79	4,670.90	-30.20	-40.77	14,540,378.45	2,046,622.86	40° 1' 49.001 N	109° 32' 56.226 W
4,767.00	1.38	213.80	4,765.87	-32.01	-42.05	14,540,376.63	2,046,621.62	40° 1' 48.983 N	109° 32' 56.242 W
4,862.00	1.50	203.14	4,860.84	-34.10	-43.17	14,540,374.51	2,046,620.53	40° 1' 48.963 N	109° 32' 56.257 W
4,957.00	1.68	198.58	4,955.81	-36.56	-44.10	14,540,372.04	2,046,619.64	40° 1' 48.938 N	109° 32' 56.269 W
5,052.00	1.64	198.41	5,050.77	-39.17	-44.98	14,540,369.41	2,046,618.81	40° 1' 48.912 N	109° 32' 56.280 W
5,147.00	1.53	191.16	5,145.73	-41.71	-45.65	14,540,366.87	2,046,618.18	40° 1' 48.887 N	109° 32' 56.289 W
5,241.00	1.48	187.43	5,239.70	-44.14	-46.05	14,540,364.43	2,046,617.82	40° 1' 48.863 N	109° 32' 56.294 W
5,336.00	1.79	184.27	5,334.66	-46.84	-46.32	14,540,361.73	2,046,617.59	40° 1' 48.837 N	109° 32' 56.297 W
5,431.00	1.73	179.85	5,429.61	-49.75	-46.43	14,540,358.81	2,046,617.53	40° 1' 48.808 N	109° 32' 56.299 W
5,526.00	1.84	180.62	5,524.57	-52.71	-46.44	14,540,355.85	2,046,617.57	40° 1' 48.779 N	109° 32' 56.299 W
5,621.00	2.04	175.07	5,619.51	-55.92	-46.31	14,540,352.65	2,046,617.75	40° 1' 48.747 N	109° 32' 56.297 W
5,716.00	2.03	174.07	5,714.45	-59.28	-45.99	14,540,349.29	2,046,618.12	40° 1' 48.714 N	109° 32' 56.293 W
5,811.00	2.28	170.21	5,809.39	-62.81	-45.50	14,540,345.77	2,046,618.67	40° 1' 48.679 N	109° 32' 56.287 W
5,906.00	2.35	167.25	5,904.31	-66.58	-44.74	14,540,342.02	2,046,619.49	40° 1' 48.642 N	109° 32' 56.277 W
6,001.00	2.49	166.77	5,999.23	-70.48	-43.84	14,540,338.12	2,046,620.45	40° 1' 48.603 N	109° 32' 56.265 W
6,096.00	2.49	165.52	6,094.14	-74.49	-42.85	14,540,334.13	2,046,621.51	40° 1' 48.563 N	109° 32' 56.253 W
6,190.00	2.56	160.35	6,188.04	-78.45	-41.64	14,540,330.20	2,046,622.79	40° 1' 48.524 N	109° 32' 56.237 W
6,285.00	2.88	161.42	6,282.94	-82.71	-40.16	14,540,325.96	2,046,624.33	40° 1' 48.482 N	109° 32' 56.218 W
6,380.00	0.14	19.22	6,377.90	-84.86	-39.37	14,540,323.82	2,046,625.16	40° 1' 48.461 N	109° 32' 56.208 W
6,475.00	2.28	355.42	6,472.87	-82.87	-39.48	14,540,325.82	2,046,625.02	40° 1' 48.481 N	109° 32' 56.209 W
6,570.00	2.09	358.30	6,567.80	-79.25	-39.68	14,540,329.43	2,046,624.76	40° 1' 48.516 N	109° 32' 56.212 W
6,664.00	1.68	357.59	6,661.75	-76.16	-39.79	14,540,332.51	2,046,624.60	40° 1' 48.547 N	109° 32' 56.213 W
6,759.00	1.21	357.74	6,756.72	-73.77	-39.89	14,540,334.91	2,046,624.46	40° 1' 48.570 N	109° 32' 56.214 W
6,853.00	0.94	347.09	6,850.70	-72.02	-40.10	14,540,336.65	2,046,624.22	40° 1' 48.588 N	109° 32' 56.217 W
6,948.00	1.92	333.91	6,945.67	-69.83	-40.97	14,540,338.82	2,046,623.31	40° 1' 48.609 N	109° 32' 56.228 W
7,043.00	1.45	327.60	7,040.63	-67.39	-42.32	14,540,341.24	2,046,621.93	40° 1' 48.633 N	109° 32' 56.246 W
7,137.00	1.22	331.06	7,134.61	-65.51	-43.44	14,540,343.10	2,046,620.78	40° 1' 48.652 N	109° 32' 56.260 W
7,232.00	2.60	349.97	7,229.55	-62.50	-44.30	14,540,346.10	2,046,619.86	40° 1' 48.682 N	109° 32' 56.271 W
7,327.00	2.32	349.89	7,324.47	-58.49	-45.02	14,540,350.10	2,046,619.08	40° 1' 48.721 N	109° 32' 56.280 W
7,421.00	1.97	353.78	7,418.40	-55.01	-45.52	14,540,353.57	2,046,618.52	40° 1' 48.756 N	109° 32' 56.287 W
7,516.00	1.51	356.68	7,513.36	-52.14	-45.77	14,540,356.44	2,046,618.22	40° 1' 48.784 N	109° 32' 56.290 W
7,611.00	1.22	351.85	7,608.33	-49.89	-45.99	14,540,358.68	2,046,617.97	40° 1' 48.807 N	109° 32' 56.293 W
7,707.00	1.26	5.66	7,704.31	-47.82	-46.03	14,540,360.75	2,046,617.90	40° 1' 48.827 N	109° 32' 56.293 W
7,801.00	1.07	17.46	7,798.29	-45.96	-45.67	14,540,362.62	2,046,618.23	40° 1' 48.845 N	109° 32' 56.289 W
7,896.00	0.81	31.46	7,893.27	-44.54	-45.05	14,540,364.05	2,046,618.82	40° 1' 48.859 N	109° 32' 56.281 W
7,991.00	1.17	40.06	7,988.26	-43.22	-44.07	14,540,365.38	2,046,619.78	40° 1' 48.872 N	109° 32' 56.268 W
8,087.00	0.99	41.09	8,084.24	-41.85	-42.90	14,540,366.77	2,046,620.93	40° 1' 48.886 N	109° 32' 56.253 W
8,182.00	0.79	48.99	8,179.23	-40.80	-41.86	14,540,367.84	2,046,621.95	40° 1' 48.896 N	109° 32' 56.240 W
8,277.00	0.72	67.99	8,274.22	-40.15	-40.82	14,540,368.51	2,046,622.98	40° 1' 48.903 N	109° 32' 56.226 W
8,372.00	0.88	69.98	8,369.21	-39.67	-39.58	14,540,369.00	2,046,624.21	40° 1' 48.907 N	109° 32' 56.210 W

Company: Kerr McGee Oil and Gas Onshore LP
Project: Uintah County, UT UTM12
Site: NBU 921-16P
Well: NBU 921-16P
Wellbore: OH
Design: OH

Local Co-ordinate Reference: Site NBU 921-16P
TVD Reference: GL 4810 & KB 19' @ 4829.00ft (PIONEER 54)
MD Reference: GL 4810 & KB 19' @ 4829.00ft (PIONEER 54)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM5000-RobertS-Local

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
8,467.00	0.87	99.76	8,464.20	-39.55	-38.18	14,540,369.15	2,046,625.61	40° 1' 48.909 N	109° 32' 56.193 W
8,562.00	0.97	119.19	8,559.19	-40.06	-36.77	14,540,368.66	2,046,627.03	40° 1' 48.904 N	109° 32' 56.174 W
8,656.00	1.23	124.20	8,653.17	-41.02	-35.24	14,540,367.73	2,046,628.57	40° 1' 48.894 N	109° 32' 56.155 W
8,751.00	1.31	143.81	8,748.15	-42.46	-33.76	14,540,366.30	2,046,630.08	40° 1' 48.880 N	109° 32' 56.136 W
8,845.00	1.55	150.85	8,842.12	-44.44	-32.50	14,540,364.35	2,046,631.37	40° 1' 48.860 N	109° 32' 56.119 W
8,941.00	1.94	157.67	8,938.08	-47.08	-31.25	14,540,361.73	2,046,632.66	40° 1' 48.834 N	109° 32' 56.103 W
9,036.00	2.06	158.87	9,033.02	-50.16	-30.03	14,540,358.67	2,046,633.94	40° 1' 48.804 N	109° 32' 56.088 W
9,131.00	2.27	159.50	9,127.95	-53.51	-28.75	14,540,355.34	2,046,635.27	40° 1' 48.771 N	109° 32' 56.071 W
9,228.00	2.47	164.92	9,224.87	-57.33	-27.53	14,540,351.54	2,046,636.54	40° 1' 48.733 N	109° 32' 56.056 W
9,323.00	2.36	159.81	9,319.78	-61.14	-26.33	14,540,347.75	2,046,637.81	40° 1' 48.695 N	109° 32' 56.040 W
9,416.00	2.04	161.02	9,412.72	-64.51	-25.13	14,540,344.41	2,046,639.07	40° 1' 48.662 N	109° 32' 56.025 W
9,511.00	1.89	152.23	9,507.66	-67.49	-23.85	14,540,341.44	2,046,640.40	40° 1' 48.632 N	109° 32' 56.008 W
9,606.00	2.54	155.02	9,602.59	-70.79	-22.23	14,540,338.17	2,046,642.07	40° 1' 48.600 N	109° 32' 55.987 W
9,702.00	2.45	153.85	9,698.50	-74.56	-20.43	14,540,334.43	2,046,643.93	40° 1' 48.563 N	109° 32' 55.964 W
9,797.00	1.77	152.43	9,793.43	-77.68	-18.85	14,540,331.34	2,046,645.56	40° 1' 48.532 N	109° 32' 55.944 W
9,892.00	1.72	156.32	9,888.39	-80.29	-17.60	14,540,328.75	2,046,646.85	40° 1' 48.506 N	109° 32' 55.928 W
9,987.00	1.52	146.33	9,983.35	-82.64	-16.33	14,540,326.42	2,046,648.16	40° 1' 48.483 N	109° 32' 55.912 W
10,082.00	1.48	135.23	10,078.32	-84.56	-14.77	14,540,324.52	2,046,649.75	40° 1' 48.464 N	109° 32' 55.891 W
10,177.00	2.18	142.04	10,173.27	-86.86	-12.79	14,540,322.26	2,046,651.77	40° 1' 48.441 N	109° 32' 55.866 W
10,273.00	2.39	152.63	10,269.19	-90.07	-10.75	14,540,319.08	2,046,653.86	40° 1' 48.409 N	109° 32' 55.840 W
10,368.00	2.66	156.31	10,364.10	-93.85	-8.95	14,540,315.33	2,046,655.72	40° 1' 48.372 N	109° 32' 55.817 W
10,463.00	2.69	155.42	10,459.00	-97.90	-7.14	14,540,311.31	2,046,657.60	40° 1' 48.332 N	109° 32' 55.793 W
10,559.00	2.50	154.28	10,554.90	-101.83	-5.29	14,540,307.41	2,046,659.51	40° 1' 48.293 N	109° 32' 55.770 W
10,654.00	2.10	158.56	10,649.82	-105.32	-3.76	14,540,303.95	2,046,661.10	40° 1' 48.259 N	109° 32' 55.750 W
10,749.00	2.54	155.62	10,744.74	-108.86	-2.25	14,540,300.44	2,046,662.66	40° 1' 48.224 N	109° 32' 55.731 W
10,844.00	2.41	152.97	10,839.66	-112.55	-0.48	14,540,296.77	2,046,664.50	40° 1' 48.187 N	109° 32' 55.708 W
10,940.00	2.32	155.41	10,935.57	-116.12	1.25	14,540,293.23	2,046,666.28	40° 1' 48.152 N	109° 32' 55.686 W
11,035.00	2.40	147.50	11,030.49	-119.54	3.12	14,540,289.84	2,046,668.21	40° 1' 48.118 N	109° 32' 55.661 W
11,130.00	2.71	153.33	11,125.40	-123.23	5.20	14,540,286.19	2,046,670.34	40° 1' 48.082 N	109° 32' 55.635 W
11,225.00	2.87	150.86	11,220.29	-127.31	7.36	14,540,282.14	2,046,672.58	40° 1' 48.041 N	109° 32' 55.607 W
LAST SDI MWD PRODUCTION SURVEY									
11,290.00	2.87	150.86	11,285.21	-130.15	8.95	14,540,279.32	2,046,674.21	40° 1' 48.013 N	109° 32' 55.587 W
SDI PROJECTION TO TD									

Design Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates		Comment
		+N/-S (ft)	+E/-W (ft)	
2,870.00	2,869.65	-21.88	-12.62	FIRST SDI MWD PRODUCTION SURVEY
11,225.00	11,220.29	-127.31	7.36	LAST SDI MWD PRODUCTION SURVEY
11,290.00	11,285.21	-130.15	8.95	SDI PROJECTION TO TD

Checked By: _____ Approved By: _____ Date: _____